



MEETING NOTICE AND AGENDA

Notice is hereby given that the Kaysville City Council will hold a regular council meeting on Thursday, February 15, 2024, starting at 7:00 PM in the **Council Chambers in Kaysville City Hall at 23 East Center Street, Kaysville, UT**. The meeting will be streamed on YouTube, and the link to the meeting will be posted on www.KaysvilleLive.com.

Public comment is only taken during a meeting for Action Items, "Call to the Public", or for a public hearing. **Those wishing to speak during these times must sign-up in person before the meeting begins.** Comments may also be directed to the City Council via email to publiccomment@kaysville.gov. Emailed comments will NOT be read out-loud at the meeting.

CITY COUNCIL Q&A – 6:30 PM

The City Council will be available to answer questions or discuss any matters the public may have.

CITY COUNCIL MEETING – 7:00 PM

The agenda shall be as follows:

- 1) OPENING
 - a) Presented by Council Member Abbigayle Hunt
- 2) CALL TO THE PUBLIC (3 MINUTE LIMIT, MUST SIGN UP IN PERSON)
- 3) PRESENTATIONS AND AWARDS
 - a) Presentation of Employee of the Quarter to Mindi Edstrom
- 4) DECLARATION OF ANY CONFLICTS OF INTEREST
- 5) CONSENT ITEMS
 - a) Authorization of FY 2025 Road Maintenance Project on 200 North Street
 - b) Approval of 200 North/Main Street Betterment Agreement with UDOT
- 6) ACTION ITEMS
 - a) Request to rezone 7.74 acres of property at 367 South Angel Street from A-5 (Heavy Agriculture) to R-1-14 (Single Family Residential) for DW Management
 - b) A Resolution amending Section 5.01 of the Personnel Rules & Regulations disciplinary procedures
- 7) WORK ITEMS
 - a) Discussion on proposed Consolidated Fee Schedule Amendment related to development review fees
 - b) Discussion on Kaysville City Center Community Reinvestment Area and the Redevelopment Agency Roles
- 8) COUNCIL MEMBERS REPORTS
- 9) CITY MANAGER REPORT
- 10) ADJOURNMENT

Kaysville City is dedicated to a policy of non-discrimination in admission to, access to, or operations of its programs, services,

or activities. If you need special assistance due to a disability, please contact the Kaysville City Offices at (801) 546-1235 at least 24 hours in advance of the meeting to be held.

I hereby certify that I posted a copy of the foregoing Notice and Agenda at Kaysville City Hall, Kaysville City website at www.kaysville.gov, and the Utah Public Notice website at www.utah.gov/pmn. Posted on February 9, 2024.

A handwritten signature in black ink, appearing to read "Annemarie Plaizier", written over a horizontal line.

Annemarie Plaizier
City Recorder

CITY COUNCIL STAFF REPORT



MEETING DATE: February 15, 2024

TYPE OF ITEM: Consent Items

PRESENTED BY: Josh Belnap

SUBJECT/AGENDA TITLE: Authorization of FY 2025 Road Maintenance Project on 200 North Street

EXECUTIVE SUMMARY:

Public Works recently bid out a project to apply preventative maintenance surface treatments on various roads and to repave 200 N from Angel St to West Davis Corridor (WDC).

Staff structured the project into 2 bid schedules so as to allow the City to either award the surface treatment and the paving to separate bidders or to the same bidder, depending on price and other applicable factors.

After reviewing the bids, staff is recommending that the Council authorize the City Manager to negotiate a contract with Advanced Paving for the surface treatment. Their bid for that work was \$379,060.

Staff is also recommending that Council authorize the City Manager to negotiate a contract with Staker Parson to repave the portion of 200 N. Staker's bid for that work was \$699,395. It is important to note that Staker is part of the contractor team who built WDC, and we met with Staker last year to talk about how the contractor team will contribute to repairs on this stretch of 200 N because of the haul truck damage from their project. That bid number does not include cost sharing, so the negotiation will identify the portion of the roadway WDC would be responsible for, thus decreasing the overall cost.

City Council Options:

1) Authorize, 2) Table

Staff Recommendation:

Authorize

Fiscal Impact:

Road utility funds

ATTACHMENTS:

1. FY 25 Roadway Maintenance Project Bid Tab

Bid Schedule A - Crack Seal/Asphalt Patch				Advanced Paving and Construction		Black Forest		Kilgore		Post Asphalt		Staker Parson	
BID ITEM	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
A. 1	Mobilization	LS	1	\$ 3,500.00	\$ 3,500.00	--	--	--	--	--	--	--	--
A. 2	Traffic Control	LS	1	\$ 7,500.00	\$ 7,500.00	--	--	--	--	--	--	--	--
A. 3	Crack Seal	LF	3,000	\$ 0.60	\$ 1,800.00	--	--	--	--	--	--	--	--
A. 4	Mastic Seal	LF	1,000	\$ 4.50	\$ 4,500.00	--	--	--	--	--	--	--	--
A. 5	Scrub Seal	SY	119,000	\$ 3.04	\$ 361,760.00	--	--	--	--	--	--	--	--
Totals				\$ 379,060.00		\$ -		\$ -		\$ -		\$ -	

Bid Schedule B - 200 N Reconstruction				Advanced Paving and Construction		Black Forest		Kilgore		Post Asphalt		Staker Parson	
BID ITEM	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
B. 1	Mobilization	LS	1	\$ 14,750.00	\$ 14,750.00	\$ 70,200.00	\$ 70,200.00	\$ 42,500.00	\$ 42,500.00	\$ 35,000.00	\$ 35,000.00	\$ 12,020.00	\$ 12,020.00
B. 2	Traffic Control	LS	1	\$ 11,650.00	\$ 11,650.00	\$ 18,300.00	\$ 18,300.00	\$ 39,200.00	\$ 39,200.00	\$ 25,000.00	\$ 25,000.00	\$ 10,500.00	\$ 10,500.00
B. 3	Remove and Replace HMA - 5"	SY	17,000	\$ 38.25	\$ 650,250.00	\$ 35.25	\$ 599,250.00	\$ 35.50	\$ 603,500.00	\$ 43.50	\$ 739,500.00	\$ 38.00	\$ 646,000.00
B. 4	Base Soft Spot Repair	SF	1,500	\$ 6.00	\$ 9,000.00	\$ 7.50	\$ 11,250.00	\$ 11.50	\$ 17,250.00	\$ 8.75	\$ 13,125.00	\$ 2.25	\$ 3,375.00
B. 5	Striping	LS	1	\$ 83,850.00	\$ 83,850.00	\$ 30,000.00	\$ 30,000.00	\$ 34,000.00	\$ 34,000.00	\$ 25,000.00	\$ 25,000.00	\$ 27,500.00	\$ 27,500.00
Totals				\$ 769,500.00		\$ 729,000.00		\$ 736,450.00		\$ 837,625.00		\$ 699,395.00	

CITY COUNCIL STAFF REPORT



MEETING DATE: February 15, 2024

TYPE OF ITEM: Consent Items

PRESENTED BY: Josh Belnap

SUBJECT/AGENDA TITLE: Approval of 200 North/Main Street Betterment Agreement with UDOT

EXECUTIVE SUMMARY:

In about 2020, Lyle Gibson (previous Community Development Director) and Mayor Tran began working on a project to improve access for vehicles and active transportation to Main St by City Hall.

As part of those efforts, Public Works was asked in 2022 to explore options to increase the number of on-street parking spaces on Center St and 100 N. Public Works engaged a consultant to explore various options that would factor in vehicle access, pedestrian access, business access and safety. We received a recommendation from the consultant, discussed the proposal with the Mayor and City Manager, and received instruction to start working on plans for implementation.

In 2021, water leaks started occurring with some frequency on 200 N. So when UDOT approached the City in July of 2023 about their intent to repave 200 N (400 W to Main) and Main St (200 N to Cherry Hill), we realized a need to coordinate a waterline replacement and the Main St parking changes with their project.

The waterline will be funded by Public Works ARPA funds (approx. \$1.43 million) and the Main St adjustments (adding curb bulb outs, signage, paint and re-working sidewalks) will be funded by Road Utility funds (approx. \$120,000).

This agreement is with UDOT for the City to pay those costs, which UDOT is not including any costs for mobilization, traffic control, or public involvement support.

City Council Options:

1) Authorize, 2) Table

Staff Recommendation:

Authorize

Fiscal Impact:

Road utility funds and ARPA funds

ATTACHMENTS:

1. Betterment Agreement

Local Agency Cost Estimate Betterment Agreement	Betterment Description: 1. Kaysville City	Estimated Cost for Betterment \$1,570,317.12
PIN: 19262 FINET/CID: 56240	Project Number: F-0273(14110 Project Name: SR-273; 200 South to I-15	Agreement Number Date Executed

THIS AGREEMENT, made and entered into the date shown below, by and between the **Utah Department of Transportation**, ("UDOT"), and null a political subdivision of the State of Utah, ("Local Agency").

Subject to the attached provisions, UDOT will include the following betterment work items into the above referenced Project and will oversee construction of the betterment work. Upon signing this Agreement, the Local Agency agrees that the costs shown below are estimates only and the Local Agency is responsible for paying all actual costs associated with these betterment items, based on Contract Unit Bid Prices, and actual quantities placed.

Detailed Description of Betterment Work:

Install bulb outs and roadway work at Center St and 100 N. Install waterline improvements along 200 N. Attached plans exhibit A , Attached Engineer estimate Exhibit B

Bid Item No.	Description	Quantity	Estimated Unit Price	Estimated Cost
	Roadway Betterment			
50	018927040 Reconstruct Valve Box	2 Each	\$1,000.00	\$2,000.00
51	01892707P Reconstruct Junction Box	1 Each	\$900.00	\$900.00
52	020567015 Granular Borrow (Plan Quantity)	77 cu yd	\$50.00	\$3,850.00
53	022217110 Remove Concrete Sidewalk	83 sq yd	\$20.00	\$1,660.00
54	022217125 Remove Concrete Curb and Gutter	212 ft	\$10.00	\$2,120.00
55	022217165 Remove Asphalt Pavement	413 sq yd	\$20.00	\$8,260.00
56	023167020 Roadway Excavation (Plan Quantity)	134 cu yd	\$50.00	\$6,700.00
57	02721702* Untreated Base Course (Plan Quantity)	51 cu yd	\$55.00	\$2,805.00
58	027417050 HMA - 1/2 inch	125 Ton	\$121.00	\$15,125.00
59	02748702* Emulsified Asphalt (Tack)	1 Ton	\$600.00	\$600.00

60	027687115	Pavement Message (Preformed Thermoplastic Stop Line, Crosswalks - 12 inch)	70	ft	\$8.00	\$560.00
61	027717059	Perpendicular/Parallel Pedestrian Access Ramp	5	Each	\$4,500.00	\$22,500.00
62	027767010	Concrete Sidewalk	754	sq ft	\$13.00	\$9,802.00
63	027767025	Concrete Curb and Gutter Type B1	292	ft	\$60.00	\$17,520.00
64	027767030	Concrete Flatwork, 4 inch thick	787	sq ft	\$11.00	\$8,657.00
65	02787702*	Bonded Wearing Course - Type B	230	sq yd	\$8.00	\$1,840.00
66	028917020	Sign Type A-1	54	sq ft	\$37.50	\$2,025.00
67	028917270	Remove Sign Less Than 20 Square Feet	2	Each	\$90.00	\$180.00
68	028917285	Relocate Sign Less Than 20 Square Feet	1	Each	\$215.00	\$215.00
69	028917320	Slipbase Sign Base (B3)	4	Each	\$500.00	\$2,000.00
70	028917365	Sign Post P3	4	Each	\$225.00	\$900.00
Waterline Betterment						
71	02511701*	Abandon Existing 16" Waterline	154	ft	\$20.00	\$3,080.00
72	02511702*	Abandon Existing 12" Waterline	2134	ft	\$15.00	\$32,010.00
73	02511703*	Abandon Existing 10" Waterline	15	ft	\$12.00	\$180.00
74	02511704*	Abandon Existing 8" Waterline	236	ft	\$10.00	\$2,360.00
75	02511705*	Abandon Existing 6" Waterline	681	ft	\$10.00	\$6,810.00
76	02511706*	Abandon Existing 4" Waterline	150	ft	\$10.00	\$1,500.00
77	02511707*	12" PVC C900 Waterline	2076	ft	\$200.00	\$415,200.00
78	02511708*	16" PVC C905 Waterline	175	ft	\$400.00	\$70,000.00
79	02511709*	12" Tee	2	Each	\$3,000.00	\$6,000.00
80	02511710*	12" X 6" Tee	8	Each	\$3,000.00	\$24,000.00
81	02511711*	16" X 14" Tee	1	Each	\$5,000.00	\$5,000.00
82	02511712*	12" X 8" Cross	2	Each	\$4,000.00	\$8,000.00
83	02511713*	12" X10" Cross	1	Each	\$4,000.00	\$4,000.00
84	02511715*	16" 45 Degree Bend	1	Each	\$4,000.00	\$4,000.00
85	02511717*	16" Water Valve	1	Each	\$8,000.00	\$8,000.00
86	02511718*	12" Water Valve	10	Each	\$5,000.00	\$50,000.00
87	02511719*	Abandon Water Valve	25	Each	\$500.00	\$12,500.00
88	02511720*	Water Service Line and Connection	7	Each	\$3,000.00	\$21,000.00
89	02511721*	Water Service Line and Connection South Side	12	Each	\$6,000.00	\$72,000.00
90	02511730*	Fire Hydrant Assembly	4	Each	\$7,000.00	\$28,000.00
91	02511731*	Fire Hydrant Assembly South Side	3	Each	\$10,000.00	\$30,000.00
92	02511732*	Remove Fire Hydrant Assembly	7	Each	\$2,500.00	\$17,500.00
93	02511740*	Connect to Existing 16" Waterline at Main Street	1	Lump	\$10,000.00	\$10,000.00

94	02511741*	Connect to Existing 14" Waterline at Main Street	1	Lump	\$30,000.00	\$30,000.00
95	02511742*	Connect to Existing Waterline at 100 West (South Side)	1	Lump	\$38,000.00	\$38,000.00
96	02511743*	Connect to Existing Waterline at 100 West (North Side)	1	Lump	\$25,000.00	\$25,000.00
97	02511744*	Connect to Existing Waterline at 200 West (South Side)	1	Lump	\$38,000.00	\$38,000.00
98	02511745*	Connect to Existing Waterline at 200 West (North Side)	1	Lump	\$25,000.00	\$25,000.00
99	02511746*	Connect to Existing Waterline at 300 West (South Side)	1	Lump	\$38,000.00	\$38,000.00
100	02511747*	Connect to Existing Waterline at 300 West (North Side)	1	Lump	\$25,000.00	\$25,000.00
101	02511748*	Connect to Existing Waterline at 400 West (South Side)	1	Lump	\$36,000.00	\$36,000.00
102	02511749*	Connect to Existing Waterline at 400 West (North Side)	1	Lump	\$20,000.00	\$20,000.00
103	02511750*	Connect to Existing Waterline at 400 West (West Side)	1	Lump	\$25,000.00	\$25,000.00
104	02511751*	Connect to Existing Waterline at STA 209+31.80	1	Lump	\$10,000.00	\$10,000.00
105	02737700P	Remove and Replace Asphalt Pavement	3009	ft	\$60.00	\$180,540.00
		Subtotal				\$1,431,899.00
		Preliminary Engineering				\$84,874.73
		Construction Engineering @ 15 %				\$53,543.39
		Total Estimated Cost of Betterment Work				\$1,570,317.12

The total estimated cost of the betterment work shall be advanced / deposited with UDOT prior to advertising / procurement of the Project. The Local Agency shall deposit the amount with UDOT's Comptroller's Office located at UDOT/Comptroller, 4501 South 2700 West, Box 141510, Salt Lake City 84119-1510.

In the event the actual betterment costs are higher, the Local Agency shall pay the additional amount required within 30 days of receiving an invoice from UDOT. In the event the actual betterment costs are lower, UDOT will refund the balance of the amount deposited within 30 days of determining the final cost of the betterment work.



Provisions

(Note: the language in these provisions shall not be changed without prior approval from the Utah AG's office)

The Local Agency desires to include the betterment work items described herein in the project contract work.

UDOT will include the Local Agency's requested betterment work in the project contract provided that the Local Agency pay the actual additional costs and UDOT's project will not be delayed because of the betterments. No betterments will be added to the bid package until this Agreement has been signed by both parties.

The Local Agency, at no cost to the Project, shall provide on-call support from Local Agency's Design Engineer or appropriate representative to correct or clarify issues during construction and to perform the necessary inspection for the Local Agency work installed by the contractor. The Local Agency engineer and / or inspector shall work with and through UDOT's Project Manager or Resident Engineer and shall give no orders directly to UDOT's contractor unless authorized in writing to do so. UDOT's contractor will accomplish the work covered herein on the Local Agency's facilities in accordance with the plans and specifications provided by the Local Agency, including changes or additions to the plans and specifications which are approved by the parties.

The Local Agency, through its inspection of the work, will provide UDOT's Project Manager or Resident Engineer with information covering any problems or concerns the Local Agency may have with acceptance of the facilities upon completion of construction.

Any periodic plan and specification review or construction inspection performed by UDOT arising out of the performance of the project does not relieve the Local Agency of its duty in the performance of this project or to ensure compliance with acceptable standards.

Except in cases of emergency, access for maintenance and servicing of the Local Agency facilities located on UDOT's right-of-way will be by permit issued by UDOT to the Local Agency, and that the Local Agency will obtain the permit and abide by the conditions thereof for policing

and other controls in the conformance with Utah Administrative Rules.

I. Indemnification:

UDOT and the Local Agency are both governmental entities subject to the Governmental Immunity Act. Each party agrees to indemnify, defend, and save harmless the other from and against all claims, suits and costs, including attorneys' fees for injury or damage of any kind, arising out of its negligent acts, errors or omissions of its officers, agents, contractors or employees in the performance of this agreement. Nothing in this paragraph is intended to create additional rights to third parties or to waive any of the provisions of the Governmental Immunity Act. The obligation to indemnify is limited to the dollar amounts set forth in the Governmental Immunity Act, provided the Act applies to the action or omission giving rise to the protections in this paragraph. The indemnification in this paragraph shall survive the expiration or termination of this Agreement.

II. Termination:

This Agreement may be terminated as follows:

- a. By mutual agreement of the parties, in writing.
- b. By either UDOT or the Local Agency for failure of the other party to fulfill their obligations as set forth in the provisions of this Agreement. Reasonable allowances will be made for circumstances beyond the control of the parties. Written notice of intent to terminate is required and shall specify the reasons for termination.
- c. By UDOT for the convenience of the State upon written notice to the Local Agency.
- d. Upon satisfactory completion of the provisions of this Agreement.

III. Maintenance:

The Local Agency agrees that, upon completion and final inspection of the project construction, to accept, own and maintain the betterment work covered herein at no further cost to UDOT.

IV. Payment and Reimbursement to UDOT:



The Local Agency shall be responsible for all actual costs associated with these betterment items.

The Local Agency agrees that if it modifies or cancels this Agreement at any time after it has been signed, the Local Agency agrees to pay any cancellation penalties or costs incurred by UDOT as a result of the betterment work scope being modified or cancelled. In the event the Local Agency fails to reimburse UDOT for the costs included in this Agreement, funding for other Local Agency projects or B&C road funds may be withheld until the entire payment is made.

V. Change in Scope and Schedule:

The Local Agency recognizes that if its project scope or schedule changes from the terms of this Agreement, Local Agency will notify the UDOT Project Manager or Resident Engineer will be notified prior to changes being made. Any costs incurred by UDOT as a result of these scope or schedule changes will be the responsibility of the Local Agency.

In the event there are changes in the scope of the work, extra work, or changes in the planned work covered by this Agreement, a signed written modification to this Agreement is required prior to the start of work on the changes or additions.

VI. Prohibition on Certain Telecommunications and Video Surveillance Services or Equipment:

All work of the Company that relates to any agreement with UDOT is subject to Public Law 115-232, Sec. 889 and 2 CFR § 200.216 (the "Telecommunications Laws"). Among other things, the Telecommunications Laws prohibit the use of any sort of "covered telecommunications" equipment or services, which are those provided by a company listed in such laws. The Company shall at all times comply with the Telecommunications Laws. The Company hereby certifies that it has read the Telecommunications Laws and consulted with legal counsel as needed. For all matters which are the subject of any agreement between the Company and UDOT, the Company hereby certifies that it currently conforms with, and will continue to conform with, the Telecommunications Laws in all respects. The

Company shall also place this certification in all UDOT-related contracts with subcontractors, consultants, and suppliers for UDOT's benefit. If any government entity having jurisdiction determines that the Company or its associates is not in compliance with the Telecommunications Laws, the Company agrees that it shall promptly notify UDOT of the same and remedy any deficiency.

VII. Miscellaneous:

This Agreement shall constitute the entire agreement and understanding of the parties with respect to the betterments, and shall supersede all offers, negotiations, and other agreements. Any amendment to this agreement must be in writing and executed by authorized representatives of each party.

Each party agrees to undertake and perform all further acts that are reasonably necessary to carry out the intent and purpose of this agreement at the request of the other party.

The failure of either party to insist upon strict compliance of any of the terms and conditions, or failure or delay by either party to exercise any rights or remedies provided in this Agreement, or by law, will not release either party from any obligations arising under this Agreement.


This Agreement may be executed in counter parts by the parties.

Each party represents that it has the authority to enter into this Agreement.

Language content was reviewed and approved by the Utah AG's office on April 10, 2018.

Local Agency			Utah Department of Transportation		
By		Date	By		Date
Title/Signature of Official			Project Manager		
By		Date	By		Date
Title/Signature of additional official, if required			Region Director		
By		Date	By		Date
Title/Signature of additional official, if required			Comptroller's Office		

EXHIBIT A



LEGEND:

- BONDED WEARING COURSE - TYPE B (1")
- HMA - 1/2 INCH (1.5") BONDED WEARING COURSE - TYPE B (1")
- SOFT SPOT REPAIR BONDED WEARING COURSE - TYPE B (1")
- ROTOMILLING
- ROTOMILLING - 1 INCH
- ROTOMILLING - 2 INCH

- RECONSTRUCT VALVE BOX
- RECONSTRUCT MANHOLE
- RECONSTRUCT CLEANOUT BOX
- RECONSTRUCT MONUMENT BOX
- RECONSTRUCT CATCH BASIN
- RECONSTRUCT UTILITY BOX

SIGN CODE LEGEND:


- N - NEW SIGN
- R - RELOCATE SIGN
- X - REMOVE SIGN

- X.X-X
- SIGN CODE
- SIGN NUMBER
- SHEET NUMBER

NOTES:

- SEE DETAIL SHEETS, DT SERIES, FOR RECONSTRUCT PEDESTRIAN ACCESS RAMP INFORMATION. SEE SUMMARY SHEETS, SM SERIES, FOR PEDESTRIAN ACCESS RAMP QUANTITIES ASSOCIATED WITH RECONSTRUCTION.
- ADJUST PAVING AROUND CURB RETURNS AND THROUGH CROSSWALK TO MEET ADA REQUIREMENTS PER UDOT 2024 STD DWGS, PA SERIES. FIELD VERIFY ADA ADJUSTMENT PROVIDES ADEQUATE DRAINAGE. EXTEND RECONSTRUCTION TO PROVIDE ADEQUATE DRAINAGE AS APPROVED BY ENGINEER.
- PAVEMENT REHABILITATION TO END ALONG EDGE OF WATERWAY, STRAIGHT ALONG THE SIDESTREET, OR AT FURTHEST CURB RETURN POINT OF CURVATURE ON SIDE STREET AS SHOWN UNLESS NOTED OTHERWISE.
- SURVEY AND REPLACE EXISTING STRIPING AND MESSAGES IN THE SAME LOCATION. SEE DETAIL SHEETS, DT SERIES, FOR PAVEMENT MARKING MATERIAL LOCATIONS.
- SEE RDDT-14A AND GRADING SHEETS, GR SERIES, FOR FULL DEPTH PAVEMENT SECTION AND BULB OUT CONSTRUCTION.

UTAH DEPARTMENT OF TRANSPORTATION				REVISIONS			
AVENUE CONSULTANTS							
APPROVED							
DRAWN BY							
QC CHECKED BY							
DATE							
PROFESSIONAL ENGINEER							
DATE							
APPROVED BY							
DATE							
REMARKS							



TBC (TOP BACK CURVE) DATA TABLE											
CURVE ID	RADIUS	LENGTH	Δ	CENTER OF CURVE				PC		PT	
	FT	FT		STATION	OFFSET	NORTHING	EASTING	STATION	OFFSET	STATION	OFFSET
A	12.50	19.47	98°21'58 RT	103+24.80	55.36 RT	537566.242	519829.639	103+24.80	42.86 RT	103+37.30	55.19 RT
B	2.50	1.96	131°49'52" RT	103+34.80	55.62 RT	537576.237	519830.157	103+37.30	55.59 RT	103+36.60	57.37 RT
C	7.50	8.30	43°56'37" RT	103+65.04	58.10 RT	537606.404	519833.389	103+61.78	64.85 RT	103+57.54	58.20 RT
D	12.50	19.81	98°21'58" RT	103+70.01	55.28 RT	537611.436	519830.693	103+57.51	55.440	103+70.02	42.78 RT

- NOTES:**
1. SEE HORIZONTAL CONTROL SHEETS, HC SERIES, FOR HORIZONTAL ALIGNMENT DATA.
 2. SEE GRADING SHEETS, GR SERIES, FOR ADDITIONAL SLOPE, ELEVATION AND PAVECUT DATA.

LEGEND:


	BONDED WEARING COURSE - TYPE B (1")
	HMA - 1/2 INCH (1.5") BONDED WEARING COURSE - TYPE B (1")
	SOFT SPOT REPAIR BONDED WEARING COURSE - TYPE B (1")
	ROTOMILLING
	ROTOMILLING - 1 INCH
	ROTOMILLING - 2 INCH

	RECONSTRUCT VALVE BOX
	RECONSTRUCT MANHOLE
	RECONSTRUCT CLEANOUT BOX
	RECONSTRUCT MONUMENT BOX
	RECONSTRUCT CATCH BASIN
	RECONSTRUCT UTILITY BOX

SIGN CODE LEGEND:

N - NEW SIGN
R - RELOCATE SIGN
X - REMOVE SIGN

	SIGN CODE SIGN NUMBER SHEET NUMBER
--	--



NOTES:

- SEE DETAIL SHEETS, DT SERIES, FOR RECONSTRUCT PEDESTRIAN ACCESS RAMP INFORMATION. SEE SUMMARY SHEETS, SM SERIES, FOR PEDESTRIAN ACCESS RAMP QUANTITIES ASSOCIATED WITH RECONSTRUCTION.
- ADJUST PAVING AROUND CURB RETURNS AND THROUGH CROSSWALK TO MEET ADA REQUIREMENTS PER UDOT 2024 STD DWGS, PA SERIES. FIELD VERIFY ADA ADJUSTMENT PROVIDES ADEQUATE DRAINAGE. EXTEND RECONSTRUCTION TO PROVIDE ADEQUATE DRAINAGE AS APPROVED BY ENGINEER.
- PAVEMENT REHABILITATION TO END ALONG EDGE OF WATERWAY, STRAIGHT ALONG THE SIDESTREET, OR AT FURTHEST CURB RETURN POINT OF CURVATURE ON SIDE STREET AS SHOWN UNLESS NOTED OTHERWISE.
- SURVEY AND REPLACE EXISTING STRIPING AND MESSAGES IN THE SAME LOCATION. SEE DETAIL SHEETS, DT SERIES, FOR PAVEMENT MARKING MATERIAL LOCATIONS.
- SEE RDDT-14A AND GRADING SHEETS, GR SERIES, FOR FULL DEPTH PAVEMENT SECTION AND BULB OUT CONSTRUCTION.
- SEE SSDT-01 FOR SIGN DETAILS.



REVISIONS

NO.	DATE	APPROVED BY	REMARKS

UTAH DEPARTMENT OF TRANSPORTATION
AVENUE CONSULTANTS

DRAWN BY	LTP
QC CHECKED BY	MMK
APPROVED	DATE
PROFESSIONAL ENGINEER	DATE

SR-273; US-89 TO I-15


19262


F-0273(14)110
ROADWAY DETAIL

PROJECT

PROJECT NUMBER

SHEET NO. RDDT-15









RETURN OF CHAIRMAN THIS DOCUMENT, AND THE EXHIBITS AND ANY INFORMATION HEREON, IS AN INSTRUMENT OF PROFESSIONAL SERVICE, IS THE PROPERTY OF J&S ENGINEERING, INC. AND IS NOT TO BE LOANED, REPRODUCED OR COPIED FOR ANY OTHER PERSON OR PURPOSE. ANY VIOLATION OF THIS POLICY WILL BE CONSIDERED A VIOLATION OF J&S ENGINEERING, INC.				TITLE: _____ PROJECT: _____ PROJECT NUMBER: _____ LAST UPDATED: _____ DRAWN BY: _____ CHECKED BY: _____ DATE: _____		 KAYSVILLE CITY CORPORATION DEVELOPMENT STANDARDS AIR RELEASE VALVE DETAILS		SHEET 6
--	--	--	--	---	--	--	--	------------

SHEET NO.	SR-273; US-89 TO I-15		UTAH DEPARTMENT OF TRANSPORTATION AVENUE CONSULTANTS				APPROVED				DRAWN BY		KV	REVISIONS																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
	PROJECT																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											
WLDLT-04	PROJECT NUMBER	F-0273(14)110	PIN	19262	PROFESSIONAL ENGINEER				QC CHECKED BY		SL	REMARKS																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
	WATERLINE DETAIL																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											




TYPICAL TRENCH UNDER EXISTING PAVEMENT IN UDOT RIGHT-OF-WAY




- NOTES:**
- GENERAL
 - VERTICAL CUTS IN ASPHALT CONCRETE MAY BE DONE BY SAW OR PAVEMENT ZIPPING. IF CUTS GREATER THAN 10 INCHES ARE NECESSARY TO PREVENT PAVEMENT "BREAK OFF", CONSULT ENGINEER FOR DIRECTIONS ON HANDLING ADDITIONAL COSTS.
 - REPAIR T-PATCH IF ANY OF THE FOLLOWING CONDITIONS OCCUR PRIOR TO FINAL PAYMENT OR AT THE END OF THE ONE YEAR CORRECTION PERIOD:
 - PAVEMENT SURFACE DISTORTION EXCEEDS 1/4 INCH DEVIATION IN 10 FEET. REPAIR OPTION - PLANE OFF SURFACE DISTORTIONS. COAT PLANED SURFACE WITH A CATIONIC OR ANIONIC EMULSION THAT COMPLIES WITH APWA SECTION 32 12 03 OR RE-MILL AND PAVE THE CUT AREA TO FILL DEPRESSIONS WITH A MINIMUM OF 2-INCHES OF NEWLAY PLACED ASPHALT.
 - SEPARATION APPEARS AT A CONNECTION TO AN EXISTING PAVEMENT OR ANY STREET FIXTURE. REPAIR OPTION - BLOW SEPARATION CLEAN AND APPLY JOINT SEALANT, APWA PLAN 265.
 - CRACKS AT LEAST 1-FOOT LONG AND 1/4-INCH WIDE OCCUR MORE OFTEN THAN 1 IN 10 SQUARE FEET. REPAIR OPTION - BLOW CLEAN AND APPLY CRACK SEAL, APWA PLAN 265.
 - PAVEMENT RAVELING IS GREATER THAN 1 SQUARE FOOT PER 100 SQUARE FEET. REPAIR OPTION - MILL AND INLAY, APWA SECTIONS 32 01 16.71 AND 32 12 05.
 - IF A SAW CUT IN THE DIRECTION OF VEHICULAR TRAVEL IS IN A WHEEL PATH, CONSULT ENGINEER FOR DIRECTIONS ON REMOVING ADDITIONAL PAVEMENT OTHER THAN THE AMOUNT SHOWN ON THE DRAWINGS.
 - PRODUCTS
 - BASE COURSE: UNTREATED BASE COURSE PER UDOT STANDARD SPECIFICATION 02721. DO NOT USE GRAVEL AS A BASE COURSE.
 - TRENCH BACKFILL: GRANULAR BACKFILL BORROW PER UDOT STANDARD SPECIFICATION 02056.
 - TACK COAT: PER UDOT STANDARD SPECIFICATION 02748.
 - ASPHALT CONCRETE: PER UDOT STANDARD SPECIFICATION 02741.
 - EXECUTION
 - BASE COURSE PLACEMENT: PER UDOT STANDARD SPECIFICATION 02721, TYPE I PLACEMENT.
 - TACK COAT. CLEAN ALL HORIZONTAL AND VERTICAL SURFACES. APPLY FULL COVERAGE ALL SURFACES.
 - ASPHALT CONCRETE: UNLESS INDICATED OTHERWISE. LIFT THICKNESS PLACEMENT IS 3-INCHES MINIMUM AFTER COMPACTION. COMPACT TO 94 PERCENT OF ASTM D 2041.

PROJECT		SR-273; US-89 TO I-15		19262-WLDT-06		SHEET NO. WLDT-06		REVISIONS	
PROJECT NUMBER		F-0273(14)110		19262		WATERLINE DETAIL		UTAH DEPARTMENT OF TRANSPORTATION AVENUE CONSULTANTS	
APPROVED		PROFESSIONAL ENGINEER		DATE		QC CHECKED BY		NO. DATE	
DRAWN BY		KV		SL		APPROVED BY		REMARKS	





- CONSTRUCTION NOTES:
1. LOCATE AND TIE INTO EX. WATERLINE. (FIELD VERIFY PIPE SIZE AND MATERIAL)
 2. ALL EXISTING UTILITY LOCATIONS ARE SHOWN FOR REFERENCE ONLY. CONTRACTOR IS TO FIELD VERIFY CONNECTION LOCATIONS PRIOR TO CONSTRUCTION, AND ALERT BOTH THE DESIGN ENGINEER AND KAYSVILLE CITY IF FIELD CONDITIONS VARY.
 3. CONTRACTOR IS RESPONSIBLE FOR ALL REPAIRS REQUIRED TO FACILITATE THE INSTALLATION OF PROPOSED UTILITIES.
 4. IF EXISTING VALVES IN THE SYSTEM MAY BE DAMAGED OR NON-FUNCTIONING. CONTRACTOR SHALL BE PREPARED TO USE NECESSARY EQUIPMENT TO ISOLATE THE SYSTEM. THIS SHOULD BE COORDINATED IN THE FIELD WITH KAYSVILLE CITY.

SR-273; US-89 TO I-15		UTAH DEPARTMENT OF TRANSPORTATION				REVISIONS					
		AVENUE CONSULTANTS									
PROJECT	F-0273(14)110		19262		APPROVED		DRAWN BY		KV		
	PIN						QC		SL		
PROJECT NUMBER	WATERLINE				PROFESSIONAL ENGINEER		DATE		CHECKED BY		
									NO.		
									DATE		
									APPROVED BY		
									REMARKS		
SHEET NO.		WL-15									



PROJECT		SR-273; US-89 TO I-15		UTAH DEPARTMENT OF TRANSPORTATION AVENUE CONSULTANTS				REVISIONS					
PROJECT NUMBER		F-0273(14)110		PIN		19262		APPROVED		DRAWN BY		KV	
WATERLINE										OC		CHECKED BY	
										SL			
										DATE		APPROVED BY	
										NO.		REMARKS	

[illegible]



12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>

12\"/>


12\"/>

12\"/>

12\"/>

WATERLINE CURVE DATA

4 R 300'
L 12.50'
PI 223+13.74 RT 28.07
PC 223+26.24 RT 27.77



CONSTRUCTION NOTES:

1. LOCATE AND TIE INTO EX. WATERLINE. (FIELD VERIFY PIPE SIZE AND MATERIAL)
2. ALL EXISTING UTILITY LOCATIONS ARE SHOWN FOR REFERENCE ONLY. CONTRACTOR IS TO FIELD VERIFY CONNECTION LOCATIONS PRIOR TO CONSTRUCTION, AND ALERT BOTH THE DESIGN ENGINEER AND KAYSVILLE CITY IF FIELD CONDITIONS VARY.
3. CONTRACTOR IS RESPONSIBLE FOR ALL REPAIRS REQUIRED TO FACILITATE THE INSTALLATION OF PROPOSED UTILITIES.
4. IF EXISTING VALVES IN THE SYSTEM MAY BE DAMAGED OR NON-FUNCTIONING. CONTRACTOR SHALL BE PREPARED TO USE NECESSARY EQUIPMENT TO ISOLATE THE SYSTEM. THIS SHOULD BE COORDINATED IN THE FIELD WITH KAYSVILLE CITY.

UTAH DEPARTMENT OF TRANSPORTATION				AVENUE CONSULTANTS			
PROJECT		PROJECT NUMBER		APPROVED		WATERLINE	
SR-273; US-89 TO I-15		F-0273(14)110		19262		PIN	
SHEET NO.		WL-18		DATE		REMARKS	
DRAWN BY		QC CHECKED BY		NO.		APPROVED BY	
KV		SL		DATE		REMARKS	
REVISIONS							

Engineer's Estimate Report
Utah Department of Transportation

PIN: 19262
Project Number: F-0273(14)110
Project Name: SR-273; US-89 to I-15
Concept: Rehabilitation High Volume
County: Davis County
Region: Region 1
Location: SR-273; MP .00 - 2.90
Bike Lane (mi): 0.00

Project Manager: Corey Nelson
Resident Engineer: Adam Hales
Designed By: Lauren Phillips
Checked By: Santiago Loaiza
Status: PS & E
Delivery Method: Design Bid Build
Estimate Number: EE-19262-001

Paved Surface Type	Quantity(sq. ft.)
Micro Surface	0
1 1/2" Treatments (HMA & SMA)	400538
2" Treatments (HMA & SMA)	0
Rehabilitation - unspecified	0
Major Rehabilitation - unspecified	0
Reconstruct - unspecified	0
Concrete Repair with Grind	0

Paved Surface Type	Quantity(sq. ft.)
Chip seal	0
1" Treatments (BWC & OGSC)	834317
Preservation - unspecified	0
3" Treatments (HMA)	0
4" Treatments (HMA)	0
> 4" Treatments (HMA)	14992
Concrete Repair	0
New PCC	0

Engineer's Estimates are UDOT Confidential until the Project is awarded and should be kept within the limits of the project team until such time

	Base Bid Items						
Container	Description						
	Line No.	Item No.	Item Name	Quantity	Unit	Unit Price	Amount
10 - ROADWAY	Base						
	1	00830701U	On the Job Training	200	Hour	\$10.00	\$2,000.00
	2	015017010	Mobilization	1	Lump	\$390,000.00	\$390,000.00
	3	01540701*	Public Information Services	1	Lump	\$10,500.00	\$10,500.00
	4	015547005	Traffic Control	1	Lump	\$110,000.00	\$110,000.00
	5	017217010	Survey	1	Lump	\$50,000.00	\$50,000.00
	6	018927010	Reconstruct Catch Basin	4	Each	\$3,500.00	\$14,000.00

Engineer's Estimate Report
Utah Department of Transportation

PIN: 19262
Project Number: F-0273(14)110

Engineer's Estimates are UDOT Confidential until the Project is awarded and should be kept within the limits of the project team until such time

	Base Bid Items					
Container	Description					
	Line No.	Item No.	Item Name	Quantity Unit	Unit Price	Amount
10 - ROADWAY	Base					
	7	018927020	Reconstruct Cleanout Box	18 Each	\$2,100.00	\$37,800.00
	8	01892702P	Reconstruct Utility Box	1 Each	\$1,000.00	\$1,000.00
	9	018927040	Reconstruct Valve Box	111 Each	\$1,000.00	\$111,000.00
	10	018927050	Reconstruct Manhole	99 Each	\$1,250.00	\$123,750.00
	11	018927060	Reconstruct Monument Box	9 Each	\$1,000.00	\$9,000.00
	12	022167001	Test-Hole Utility	15 Each	\$800.00	\$12,000.00
	13	022217125	Remove Concrete Curb and Gutter	367 ft	\$10.00	\$3,670.00
	14	027377001	Asphalt Pavement Soft Spot Repair - Contingency Item	522 cu yd	\$325.00	\$169,650.00
	15	027377002	UTBC Soft Spot Repair - Contingency Item	293 cu yd	\$100.00	\$29,300.00
	16	027377003	Borrow Soft Spot Repair - Contingency Item	220 cu yd	\$100.00	\$22,000.00
	17	02737701P	Asphalt Pavement Soft Spot Repair	381 cu yd	\$325.00	\$123,825.00
	18	02737702P	UTBC Soft Spot Repair	321 cu yd	\$100.00	\$32,100.00
	19	02737703P	Borrow Soft Spot Repair	480 cu yd	\$100.00	\$48,000.00
	20	027417050	HMA - 1/2 inch	3748 Ton	\$121.00	\$453,508.00
	21	02748702*	Emulsified Asphalt (Tack)	67 Ton	\$600.00	\$40,200.00
	22	027717087	Replace Detectable Warning Surface	10 Each	\$1,250.00	\$12,500.00
	23	027717110	Reconstruct Pedestrian Access Ramp	31 Each	\$8,750.00	\$271,250.00
	24	027767025	Concrete Curb and Gutter Type B1	367 ft	\$60.00	\$22,020.00
	25	02787702*	Bonded Wearing Course - Type B	137132 sq ft	\$8.00	\$1,097,056.00
	26	029617010	Rotomilling	22588 sq yd	\$4.00	\$90,352.00
	27	029617020	Rotomilling - 1 Inch	2407 sq yd	\$2.00	\$4,814.00
	28	029617030	Rotomilling - 2 Inch	40822 sq yd	\$3.00	\$122,466.00

Engineer's Estimate Report
Utah Department of Transportation

PIN: 19262
Project Number: F-0273(14)110

Engineer's Estimates are UDOT Confidential until the Project is awarded and should be kept within the limits of the project team until such time

	Base Bid Items					
Container	Description					
	Line No.	Item No.	Item Name	Quantity Unit	Unit Price	Amount
10 - ROADWAY	Base					
	29	029837010	Grinding for Grooved-In Pavement Markings	70445 ft	\$0.50	\$35,222.50
20 - STRUCTURES	C 893R					
	30	03372701*	Thin Bonded Polymer Overlay, Type I	30195 sq ft	\$7.00	\$211,365.00
	31	03372703*	Polymer Overlay Removal	30195 sq ft	\$3.00	\$90,585.00
	32	03392703*	Parapet Sealing	635 ft	\$16.00	\$10,160.00
	33	039347010	Structural Pothole Patching	1510 sq ft	\$55.00	\$83,050.00
40 - SIGNING	Base					
	34	02767701*	4 Inch Pavement Marking Wet Retroreflective Tape - White	8171 ft	\$4.50	\$36,769.50
	35	02767702*	8 Inch Pavement Marking Wet Retroreflective Tape - White	6228 ft	\$9.00	\$56,052.00
	36	02767703*	4 Inch Pavement Marking Wet Retroreflective Tape - Yellow	28954 ft	\$4.50	\$130,293.00
	37	027687030	4 inch Pavement Marking Epoxy - White Type 1	24786 ft	\$6.00	\$148,716.00
	38	027687040	4 inch Pavement Marking Epoxy - Yellow Type 1	2306 ft	\$6.00	\$13,836.00
	39	027687105	Pavement Message (Preformed Thermoplastic)	161 Each	\$200.00	\$32,200.00
	40	027687115	Pavement Message (Preformed Thermoplastic Stop Line, Crosswalks - 12 inch)	5478 ft	\$8.00	\$43,824.00
	41	02768712P	Pavement Message (Preformed Thermoplastic Stop Line, Crosswalks - 24 inch)	585 ft	\$16.00	\$9,360.00
	42	028917020	Sign Type A-1	142 sq ft	\$37.50	\$5,325.00
	43	028917075	Sign Type A-2	218 sq ft	\$40.00	\$8,720.00

**Engineer's Estimate Report
Utah Department of Transportation**

PIN: 19262
Project Number: F-0273(14)110

Engineer's Estimates are UDOT Confidential until the Project is awarded and should be kept within the limits of the project team until such time

	Base Bid Items					
Container	Description					
	Line No.	Item No.	Item Name	Quantity Unit	Unit Price	Amount
40 - SIGNING	Base					
	44	028917270	Remove Sign Less Than 20 Square Feet	16 Each	\$90.00	\$1,440.00
	45	028917300	Small Sign Tubular Steel Post Base (B1)	72 Each	\$275.00	\$19,800.00
	46	028917320	Slipbase Sign Base (B3)	4 Each	\$500.00	\$2,000.00
	47	028917360	Sign Post P2	72 Each	\$175.00	\$12,600.00
	48	028917365	Sign Post P3	4 Each	\$225.00	\$900.00
50 - SIGNALS	Base					
	49	02892701D	Traffic Signal System (SR-273 & 200 East)	1 Lump	\$3,500.00	\$3,500.00
80 - NON-PARTICIPATING	Roadway Betterment					
	50	018927040	Reconstruct Valve Box	2 Each	\$1,000.00	\$2,000.00
	51	01892707P	Reconstruct Junction Box	1 Each	\$900.00	\$900.00
	52	020567015	Granular Borrow (Plan Quantity)	77 cu yd	\$50.00	\$3,850.00
	53	022217110	Remove Concrete Sidewalk	83 sq yd	\$20.00	\$1,660.00
	54	022217125	Remove Concrete Curb and Gutter	212 ft	\$10.00	\$2,120.00
	55	022217165	Remove Asphalt Pavement	413 sq yd	\$20.00	\$8,260.00
	56	023167020	Roadway Excavation (Plan Quantity)	134 cu yd	\$50.00	\$6,700.00
	57	02721702*	Untreated Base Course (Plan Quantity)	51 cu yd	\$55.00	\$2,805.00
	58	027417050	HMA - 1/2 inch	125 Ton	\$121.00	\$15,125.00
	59	02748702*	Emulsified Asphalt (Tack)	1 Ton	\$600.00	\$600.00
	60	027687115	Pavement Message (Preformed Thermoplastic Stop Line, Crosswalks - 12 inch)	70 ft	\$8.00	\$560.00
	61	027717059	Perpendicular/Parallel Pedestrian Access Ramp	5 Each	\$4,500.00	\$22,500.00

Engineer's Estimate Report
Utah Department of Transportation

PIN: 19262
Project Number: F-0273(14)110

Engineer's Estimates are UDOT Confidential until the Project is awarded and should be kept within the limits of the project team until such time

	Base Bid Items					
Container	Description					
	Line No.	Item No.	Item Name	Quantity Unit	Unit Price	Amount
80 - NON-PARTICIPATING	Roadway Betterment					
	62	027767010	Concrete Sidewalk	754 sq ft	\$13.00	\$9,802.00
	63	027767025	Concrete Curb and Gutter Type B1	292 ft	\$60.00	\$17,520.00
	64	027767030	Concrete Flatwork, 4 inch thick	787 sq ft	\$11.00	\$8,657.00
	65	02787702*	Bonded Wearing Course - Type B	230 sq yd	\$8.00	\$1,840.00
	66	028917020	Sign Type A-1	54 sq ft	\$37.50	\$2,025.00
	67	028917270	Remove Sign Less Than 20 Square Feet	2 Each	\$90.00	\$180.00
	68	028917285	Relocate Sign Less Than 20 Square Feet	1 Each	\$215.00	\$215.00
	69	028917320	Slipbase Sign Base (B3)	4 Each	\$500.00	\$2,000.00
	70	028917365	Sign Post P3	4 Each	\$225.00	\$900.00
80 - NON-PARTICIPATING	Waterline Betterment					
	71	02511701*	Abandon Existing 16" Waterline	154 ft	\$20.00	\$3,080.00
	72	02511702*	Abandon Existing 12" Waterline	2134 ft	\$15.00	\$32,010.00
	73	02511703*	Abandon Existing 10" Waterline	15 ft	\$12.00	\$180.00
	74	02511704*	Abandon Existing 8" Waterline	236 ft	\$10.00	\$2,360.00
	75	02511705*	Abandon Existing 6" Waterline	681 ft	\$10.00	\$6,810.00
	76	02511706*	Abandon Existing 4" Waterline	150 ft	\$10.00	\$1,500.00
	77	02511707*	12" PVC C900 Waterline	2076 ft	\$200.00	\$415,200.00
	78	02511708*	16" PVC C905 Waterline	175 ft	\$400.00	\$70,000.00
	79	02511709*	12" Tee	2 Each	\$3,000.00	\$6,000.00
	80	02511710*	12" X 6" Tee	8 Each	\$3,000.00	\$24,000.00
	81	02511711*	16" X 14" Tee	1 Each	\$5,000.00	\$5,000.00
	82	02511712*	12" X 8" Cross	2 Each	\$4,000.00	\$8,000.00
	83	02511713*	12" X10" Cross	1 Each	\$4,000.00	\$4,000.00

Engineer's Estimate Report
Utah Department of Transportation

PIN: 19262
Project Number: F-0273(14)110

Engineer's Estimates are UDOT Confidential until the Project is awarded and should be kept within the limits of the project team until such time

	Base Bid Items						
Container	Description						
	Line No.	Item No.	Item Name	Quantity	Unit	Unit Price	Amount
80 - NON-PARTICIPATING	Waterline Betterment						
	84	02511715*	16" 45 Degree Bend	1	Each	\$4,000.00	\$4,000.00
	85	02511717*	16" Water Valve	1	Each	\$8,000.00	\$8,000.00
	86	02511718*	12" Water Valve	10	Each	\$5,000.00	\$50,000.00
	87	02511719*	Abandon Water Valve	25	Each	\$500.00	\$12,500.00
	88	02511720*	Water Service Line and Connection	7	Each	\$3,000.00	\$21,000.00
	89	02511721*	Water Service Line and Connection South Side	12	Each	\$6,000.00	\$72,000.00
	90	02511730*	Fire Hydrant Assembly	4	Each	\$7,000.00	\$28,000.00
	91	02511731*	Fire Hydrant Assembly South Side	3	Each	\$10,000.00	\$30,000.00
	92	02511732*	Remove Fire Hydrant Assembly	7	Each	\$2,500.00	\$17,500.00
	93	02511740*	Connect to Existing 16" Waterline at Main Street	1	Lump	\$10,000.00	\$10,000.00
	94	02511741*	Connect to Existing 14" Waterline at Main Street	1	Lump	\$30,000.00	\$30,000.00
	95	02511742*	Connect to Existing Waterline at 100 West (South Side)	1	Lump	\$38,000.00	\$38,000.00
	96	02511743*	Connect to Existing Waterline at 100 West (North Side)	1	Lump	\$25,000.00	\$25,000.00
	97	02511744*	Connect to Existing Waterline at 200 West (South Side)	1	Lump	\$38,000.00	\$38,000.00
	98	02511745*	Connect to Existing Waterline at 200 West (North Side)	1	Lump	\$25,000.00	\$25,000.00
	99	02511746*	Connect to Existing Waterline at 300 West (South Side)	1	Lump	\$38,000.00	\$38,000.00
	100	02511747*	Connect to Existing Waterline at 300 West (North Side)	1	Lump	\$25,000.00	\$25,000.00
	101	02511748*	Connect to Existing Waterline at 400 West (South Side)	1	Lump	\$36,000.00	\$36,000.00
	102	02511749*	Connect to Existing Waterline at 400 West (North Side)	1	Lump	\$20,000.00	\$20,000.00

Engineer's Estimate Report
Utah Department of Transportation

PIN: 19262
Project Number: F-0273(14)110

Engineer's Estimates are UDOT Confidential until the Project is awarded and should be kept within the limits of the project team until such time

	Base Bid Items					
Container	Description					
	Line No.	Item No.	Item Name	Quantity	Unit	Unit Price
80 - NON-PARTICIPATING	Waterline Betterment					
	103	02511750*	Connect to Existing Waterline at 400 West (West Side)	1	Lump	\$25,000.00
	104	02511751*	Connect to Existing Waterline at STA 209+31.80	1	Lump	\$10,000.00
	105	02737700P	Remove and Replace Asphalt Pavement	3009	ft	\$60.00
180 - TIME AND/OR LANE RENTAL	Base					
	106	00221700*	Contract Time	120	Cal d	\$2,130.00
Base Bid Items Sub Total						\$6,056,978.00

**Engineer's Estimate Report
Utah Department of Transportation**

PIN: 19262
Project Number: F-0273(14)110

Engineer's Estimates are UDOT Confidential until the Project is awarded and should be kept within the limits of the project team until such time

	Base Non Bid Items					
Container	Description					
	Line No.	Item No.	Item Name	Quantity	Unit	Unit Price
						Amount
77 - MISC NON-BID: UDOT CONTINGENCY FUND	Base					
	107	00007277*	UDOT Contingency Fund	1	Lump	\$280,000.00
79 - NON BID: INCENTIVES	Base					
	108	00007601*	Pavement Smoothness Incentive	1	Lump	\$69,000.00
	109	00007602*	Hot Mix Asphalt (HMA) Incentive	1	Lump	\$14,000.00
	110	00007605*	Bonded Wearing Course Incentive	1	Lump	\$13,000.00
	111	00007606*	Early Completion - Time	5	Cal d	\$2,130.00
90 - STATE FURNISHED	Base					
	112	028927047	Signal State Furnished Materials	1	Lump	\$540.60
95 - CONSTRUCTION ENGINEERING	Base					
	113	00007910*	In-House	1	Lump	\$20,000.00
	114	00007911*	Consultant C.E.	1	Lump	\$356,955.95
97 - PRELIMINARY ENGINEERING	Base					
	115	00007201*	In-House	1	Lump	\$20,000.00
	116	00007202*	Consultant	1	Lump	\$226,550.48
Base Non Bid Items Sub Total						\$1,010,697.03

Container Summary

<i>Bid</i>		
10 - ROADWAY	Base	\$3,448,983.50
20 - STRUCTURES	C 893R	\$395,160.00
40 - SIGNING	Base	\$521,835.50
50 - SIGNALS	Base	\$3,500.00
80 - NON-PARTICIPATING	Roadway Betterment	\$110,219.00
80 - NON-PARTICIPATING	Waterline Betterment	\$1,321,680.00

Engineer's Estimate Report
Utah Department of Transportation

PIN: 19262
Project Number: F-0273(14)110

Engineer's Estimates are UDOT Confidential until the Project is awarded and should be kept within the limits of the project team until such time

180 - TIME AND/OR LANE RENTAL	Base	\$255,600.00
-------------------------------	------	--------------

Non-Bid

77 - MISC NON-BID: UDOT CONTINGENCY FUND	Base	\$280,000.00
79 - NON BID: INCENTIVES	Base	\$106,650.00
90 - STATE FURNISHED	Base	\$540.60
95 - CONSTRUCTION ENGINEERING	Base	\$376,955.95
97 - PRELIMINARY ENGINEERING	Base	\$246,550.48

Engineer's Estimate Summary

Base Bid	\$6,056,978.00
Base Non Bid	\$1,010,697.03
Less Base Time and/or Lane Rental	\$255,600.00
Less Base Innovative Contracting	\$0.00
Base Total	\$6,812,075.03
Base Bid Total	\$5,801,378.00
Additive Bid	\$0.00
Additive Non Bid	\$0.00
Less Additive Time and/or Lane Rental	\$0.00
Less Additive Innovative Contracting	\$0.00
Additive Total	\$0.00
Additive Bid Total	\$0.00
Engineer's Estimate Bid Items Total	\$5,801,378.00

CITY COUNCIL STAFF REPORT



MEETING DATE: February 15, 2024

TYPE OF ITEM: Action Item

PRESENTED BY: Melinda Greenwood, Community Development Director

SUBJECT/AGENDA TITLE: Request to rezone 7.74 acres of property at 367 South Angel Street from A-5 (Heavy Agriculture) to R-1-14 (Single Family Residential) for DW Management

EXECUTIVE SUMMARY:

The property at 367 South Angel Street is before the Council for consideration of a rezone from A-5 to R-1-14. In late 2023, this same property was under consideration for a rezone to R-1-20, but the applicant withdrew their application prior to the City Council meeting, and has now submitted an application for R-1-14.

The Planning Commission held a public hearing at their January 25, 2024, meeting. During the hearing, a resident spoke on behalf of the neighboring subdivision, and expressed opposition to the R-1-14 zoning. No reason was provided for their opposition. One other comment (attached) was submitted to the Planning Commission, opposing the development in hopes of keeping the property rural and expressing concerns about traffic on Angel Street.

The Planning Commission voted 6-0 to send the City Council a recommendation of approval for the rezone application.

City Council Options:

1. Approve the rezone request for 7.74 acres of property located at 367 South Angel Street from A-5 (Heavy Agriculture) to R-1-14 (Single Family Residential).
2. Deny the rezone request.

Staff Recommendation:

Based on the Planning Commission's recommendation of approval, staff recommends approval of the rezone request for 7.74 acres of property located at 367 South Angel Street from A-5 (Heavy Agriculture) to R-1-14 (Single Family Residential).

Fiscal Impact:

N/A

ATTACHMENTS:

1. PC Staff Report RZN R-1-14 367 South Angel Street 1.25.24
 2. Planning Commission Meeting Minutes 1-25-24
 3. Public Comment_ Rose Zukley 1-10-24
 4. Ordinance for Rezone 367 South Angel Street R-1-14
-

PLANNING COMMISSION STAFF REPORT

To: Kaysville City Planning Commission
From: Dan Jessop, Zoning Administrator
Date: January 17, 2024

Agenda Item #3: Rezone request and Public Hearing for property at 367 South Angel Street from A-5 (Heavy Agriculture) to R-1-14 (Single Family 14,000 ft²) for applicant DW Management

Meeting Date	January 25, 2024
Application Type	Rezone
Applicant Owner	DW Management
Address Parcel ID Number	367 South Angel Street 08-009-0069
Lot Size	7.74 acres 337,154 ft ²
Current Use	Agriculture Single Family
Current Zoning	A-5
Density Entitlement	1 lot
Requested Zoning	R-1-14
Density Entitlement	24 lots

1. BACKGROUND


The property currently is a 7.74 acre parcel with a single-family dwelling on it. The property was the Paul Webster Farm. The parcel was brought before the November 9, 2023 Planning Commission with a rezone application for R-1-20. The applicant then pulled the application prior to the City Council taking action and has since submitted a rezone application for R-1-14. The parcel meets the square footage and frontage for the proposed R-1-14 zone.



2. SURROUNDING LAND USE AND ZONING

The parcel is located on the south end of Angel Street. The application submitted to the Planning Commission for consideration of rezone to R-1-14 is appropriate for the location. The characteristics of the surrounding area and neighborhood are provided.


- **Adjacent** – Directly adjacent to the subject property is R-1-20, A-5, and R-A.
- **North** – The subject property is bordered by R-1-20.
- **South** – Directly south of the parcel is A-5.
- **East** – It is R-1-20 with established single-family dwellings.
- **West** – Across Angel Street from the subject property is established single family homes which are zoned R-A and R-1-20.



3. GENERAL PLAN

The future land use map in the 2022 General Plan shows the property at 367 South Angel Street to be in a Single-Family Dwelling district. The rezone request to R-1-14 is supported by the Future Land Use Map. The yellow color indicates the single family zoning on the future land map below. The rezone from A-5 to R-1-14 would provide more single-family lots, which is consistent with the setbacks of R-1-20, which is zoning district for the majority of the established neighborhoods on the east side of Angel Street. On page 27 of our 2022 General Plan Goal 1 is to preserve and protect Kaysville's "Small Town" atmosphere by limiting change in functioning neighborhood districts. The R-1-14 will provide lots that will accommodate similar houses with the same street appeal, look, and feel as the houses in the less dense R-1-20 adjacent to the proposed rezone.

The Goal to preserve neighborhood character on page 43 Chapter 2 Transportation and Connectivity, goal 3.2 shows we should use the street design to shape the neighborhood character which this rezone reflects. The entire Angel Street aligns with the goals, and the provisions support the proposed rezone. On page 49 of the general plan, it promotes affordability. The smaller lots would fill the gap between R-1-20, and smaller lots on the north end of Angel Street. Last but




not least, it will promote the objective on page 54 objective 1.3 allowing for a slightly higher density.

Staff believes the rezone is supported by the 2022 General Plan. The Future Land Use map is clear that the area is complementary to the zone change.

4. PUBLIC COMMENT

A total of 55 public notices were mailed to property owners within 500’ radius of the subject property from two places and a sign was placed on the property on Friday January 19, 2024. We have received one comment as of January 10, 2024. The comment is opposing the development of the green space to the south of the Mountain Vistas Subdivision and desires it stay rural farm land. The resident also had concerns about traffic capacity on Angel Street.



5. RECOMMENDATION

Staff is recommending approval of the zone change from A-5 to R-1-14 with support from the 2022 General Plan as a compatible zone for the existing homes and neighborhood character.

The Planning Commission may make a recommendation to the City Council to approve or deny the rezone request.

Kaysville City Planning Commission Meeting Minutes

January 25, 2024

The Planning Commission meeting was held on Thursday, January 25, 2024 at 7:00 pm in the Kaysville City Hall located at 23 East Center Street.

Planning Commission Members in Attendance: Chair Steve Lyon, Commissioners Mike Packer, Wilf Sommerkorn, Debora Shepard, Megan Sevy, and Paul Allred

Planning Commissioners Absent: Commissioner Erin Young

Staff Present: Dan Jessop and Mindi Edstrom

Public Attendees: City Councilmember Abbi Hunt, Laurene Starkey, Jill Dredge, Dale Webster, and Robert Chilchrist

1- WELCOME AND MEETING ORDER

Chair Lyon opened the meeting by welcoming all in attendance to the January 25, 2024 Planning Commission meeting.

2- DECLARATION OF CONFLICTS OF INTEREST

There were no declarations of conflicts of interest from the Commissioners.

3- REZONE REQUEST AND PUBLIC HEARING FOR PROPERTY AT 367 SOUTH ANGEL STREET FROM A-5 (HEAVY AGRICULTURE) TO R-1-14 (SINGLE FAMILY 14,000 FT²) FOR APPLICANT DW MANAGEMENT

Dan Jessop introduced agenda item three for a rezone at 367 South Angel Street from A-5 Heavy Agricultural to R-1-14 Single Family with 14,000 ft² lots. Mr. Jessop said a R-1-20 rezone proposal for this property was before Commissioners on November 9, 2023 and they gave a recommendation for approval for City Council. The rezone was on the City Council agenda on December 7, 2023, but the applicant pulled the rezone application because they decided they wanted to go with the R-1-14 zone instead of an R-1-20 zone. Mr. Jessop said the rezone is consistent with the neighborhood and the Kaysville City General Plan. He explained that the R-1-14 zone is a smaller lot area reduced from 20,000 ft² lots to 14,000 ft², however all the setbacks and frontages will be the same as R-1-20, the lots would just have smaller backyards. He explained that from the road view there would not be any visible differences.

Commissioner Allred asked what the net increase in lots would be by going to R-1-14.

Dale Webster, the applicant, said the increase would be 18 lots to 24 lots with R-1-14. He said if a road is required they would need to downsize two of the lots on the south side because of the piece of land to the east is owned by another property owner which impinges two different lots so they would lose another two lots. Mr. Webster said if he went with smaller lots they could get a few more homes or at least the same amount of homes from the R-1-20 rezone. Commissioner Allred said the answer to his question would be approximately a 25 percent

increase because of the rezone change.

Mr. Webster said it is going to be the same amount of lots as it was initially, however he could possibly lose four lots to a road on the south side.

Chair Lyon asked about a connector road to Galbraith Drive.

Mr. Webster said that it is not a discussion at this point.

Chair Lyon opened up the Public Hearing and reminded the public to keep comments to three minutes and to state your name and the city they live in.

Robert Chilchrist, a Kaysville resident, said he represents several residents from the Mountain Vista Subdivision. Mr. Chilchrist said they would like the Planning Commission and City Council to know they would like this project to have a road in between where the Mountain Vistas Road stops and in between the 27-acre field to the south simply for safety and access purposes for now and future developments. He also said that the neighbors were all in favor with the R-1-20 rezone when they were going to be half acre lots but they are not ok with it being rezoned R-1-14.

Chair Lyon closed the Public Hearing.

Commissioner Allred said he feels this is a prime missed opportunity for density on the west side of Kaysville and feels that we need more density and diversity with housing.

Commissioner Sommerkorn said that the only difference from R-1-20 to the R-1-14 zone is that the backyards will be smaller and from the road the lots will appear the same size.

Commissioner Packer said that it is very forward thinking to have a road stubbed out on the south property and is in support of a connector road.

Commissioner Sommerkorn also agrees with Commissioner Packer regarding the connector road.

Chair Lyon said a connector road would be good for circulation, safety and removes burden from the connecting neighborhoods.

Commissioner Allred made a motion to recommend approval of the rezone to City Council for DW Management for 7.74 acres at 367 South Angel Street from A-5 Heavy Agricultural to R-1-14 Single Family based on the staff recommendations and the fact that the proposal complies with the city's General Plan. Commissioner Sommerkorn seconded the motion and the vote was unanimous in favor of the motion (6-0).

Commissioner Allred: Yay

Commissioner Shepard: Yay
Commissioner Lyon: Yay
Commissioner Packer: Yay
Commissioner Sevy: Yay
Commissioner Sommerkorn: Yay

4- APPROVAL OF THE MINUTES FROM THE DECEMBER 14, 2023 AND JANUARY 11, 2024 PLANNING COMMISSION

Chair Lyon asked for a voice vote for the minutes from December 14, 2023. Commissioner Allred abstained from the vote as he was not present at that meeting. All voted in favor of approving the minutes (5-0).

Commissioner Allred: Abstained
Commissioner Shepard: Yay
Commissioner Lyon: Yay
Commissioner Packer: Yay
Commissioner Sevy: Yay
Commissioner Sommerkorn: Yay

Chair Lyon asked for a voice vote for the minutes from January 11, 2024. All voted in favor of approving the minutes (6-0).

Commissioner Allred: Yay
Commissioner Shepard: Yay
Commissioner Lyon: Yay
Commissioner Packer: Yay
Commissioner Sevy: Yay
Commissioner Sommerkorn: Yay

5- OTHER MATTERS THAT PROPERLY COME BEFORE THE PLANNING COMMISSION

Chair Lyon announced Commissioner Shepard as the new Commissioner Vice-Chair.

Commissioner Sommerkorn said there will be an online Planning Commission Chair training in the coming weeks for Commissioners and would let the group know about it.

Ms. Edstrom gave a brief explanation of the new subdivision process.

Commissioner Sommerkorn said that the change in the subdivision process is short sided by the state and that the concept plan was a place where you get an opportunity to look at the layout and the design and get ideas and thought it was very helpful.

6- ADJOURNMENT

Commissioner Allred motioned to adjourn and Commissioner Young seconded the motion. The meeting ended at 7:24 pm.

From: noreply@civicplus.com
To: [Melinda Greenwood](#); [Mindi Edstrom](#); [Dan Jessop](#); [REDACTED]
Subject: Online Form Submittal: Contact the Planning Commission
Date: Wednesday, January 10, 2024 6:19:35 PM

Contact the Planning Commission

Have a question or comment? Want to contact the Planning Commission about an upcoming item on a meeting? Please fill out the form below and an e-mail will be sent to all of the Planning Commission members. You can also contact the Community Development office at 801-546-1241.

Name	Rose Zukley
Email Address	[REDACTED]
Address	[REDACTED]
City	[REDACTED]
State	[REDACTED]
Zip Code	[REDACTED]
Phone Number	[REDACTED]
Your Message	Regarding Zone Change at 367 South Angel (25 January hearing): One of the primary reasons my husband and I moved to Kaysville and particularly Angel street was the mix of both residential housing and rural farming. Over the last two years that mixture has changed. Additionally, the requested change seems to ignore that Angel is a two lane street that is not designed for the increased traffic flow created by the previously approved changes (not including this change) nor the other supporting infrastructure that would need an increase. I would request the committee deny this change as it fundamentally changes the heart of Kaysville - the mixture of rural and residential.
Upload an Attachment	Field not completed.
Upload an Attachment	Field not completed.
Upload an Attachment	Field not completed.

ORDINANCE NO. 24-XX-XX

AN ORDINANCE REZONING 367 SOUTH ANGEL STREET, A CERTAIN PORTION OF KAYSVILLE CITY TO THE R-1-14 RESIDENTIAL SINGLE FAMILY; HEREINAFTER FULL DESCRIBED PROVIDING FOR REPEALER; PROVIDEING FOR SEVERABILITY; AND PROVIDING FOR AN EFFECTIVE DATE

WHEREAS, the City Council of Kaysville City, State of Utah, has determined in an open public meeting to rezone the subject property at 367 South Angel Street from A-5 Heavy Agriculture to a R-1-14 Residential Single Family; and

WHEREAS, said meeting was duly and regularly held and the interested parties were given an opportunity to be heard; and

WHEREAS, on January 25, 2024, with a vote of 6-0, the Kaysville City Planning Commission made a recommendation of approval to the City Council of the zone change to R-1-14 Residential Single Family; and

WHEREAS, the City Council, after due consideration of said district, has concluded that it is in the best interest of the City and the inhabitants thereof that said R-1-14 Residential Single Family zone be implemented;

NOW, THEREFORE, BE IT ORDAINED BY THE CITY COUNCIL OF KAYSVILLE CITY, UTAH:

SECTION I: Repealer. If any provisions of the City's Code previously adopted are inconsistent herewith they are hereby repealed.

SECTION II: Rezone. The real property at 367 South Angel Street, and known by Parcel Identification Number 08-009-0069, as shown on the attached map which is made a part hereof, containing approximately 7.74 acres (337,154 ft²) of land, shall be rezoned and the Zoning Map amended; and

SECTION III: Severability. If any section, subsection, sentence, clause or phrase of this ordinance is declared invalid or unconstitutional by a court of competent jurisdiction, said portion shall be severed and such declaration shall not affect the validity of the remainder of this ordinance.

SECTION VI: This Ordinance shall take effect upon execution of the ordinance.

PASSED AND ADOPTED by the City Council of Kaysville City, Utah, this February 15, 2024.

Tamara Tran
Mayor

ORDINANCE NO. 24-XX-XX

ATTEST:

Annemarie Plaizier
City Recorder

CITY COUNCIL STAFF REPORT



MEETING DATE: February 15, 2024

TYPE OF ITEM: Action Item

PRESENTED BY: Nic Mills

SUBJECT/AGENDA TITLE: A Resolution amending Section 5.01 of the Personnel Rules & Regulations disciplinary procedures

EXECUTIVE SUMMARY:

This amendment would expand the ability to give written reprimands to authorized supervisors. City policy anticipates graduated sanctions for employee misconduct. The current sanctions (ordered from least to most severe) are: Verbal Warning, Written Reprimand, Suspension, Demotion, and Dismissal. Under the current policy, supervisors can give Verbal Warnings only. This amendment would allow Department Heads to authorize supervisors to give written reprimands.

The proposed policy include two oversight functions. First, Department Heads needs to authorize which supervisors may issue written reprimands. Second, the Department Head needs to agree that the misconduct warrants a written reprimand. City Staff believes that this change appropriately balances the need to maintain high-standards of employee conduct, whilst freeing Department Heads from having to handle every situation requiring this low-level of discipline.

City Council Options:

1) Approve the resolution as written; 2) Approve the resolution with any modifications that the Council deems appropriate; 3) Decline to approve the resolution and remand to staff with further direction.

Staff Recommendation:

Staff recommends that the City Council approve this resolution.

Fiscal Impact:

None anticipated.

ATTACHMENTS:

1. Resolution - Personnel Rules & Regulations
-

RESOLUTION 24-XX-XX

A RESOLUTION AMENDING SECTION 5.01 OF THE PERSONNEL RULES & REGULATIONS REGARDING DISCIPLINARY PROCEDURES

WHEREAS, the Kaysville City Council desires that City Personnel are afforded a fair and just procedure when they need to to improve their conduct; and

WHEREAS, the City Council desires to allow supervisors the ability to address conduct at early stages to insure the that misconduct is handled efficiently, expeditiously, and discreetly; and

WHEREAS, it is deemed to be in the best interest of the citizens of Kaysville City to adopt and approve the policy outlined below.

NOW, THEREFORE, BE IT RESOLVED BY THE CITY COUNCIL OF KAYSVILLE, UTAH:

The Kaysville City Personnel Policies and Procedures Section 5.03 shall be amended as followed:

5.01 Disciplinary Procedure

...

WRITTEN REPRIMAND - A department head , or an authorized supervisor with the department head's concurrence, may reprimand an employee in writing. Such reprimand should be addressed to the employee and a signed copy should be delivered to ~~the Personnel Officer~~ Human Resources for inclusion in the employee's personnel file.

...

PASSED AND ADOPTED by the City Council of Kaysville, Utah, this ____ day of _____, 2024.

ATTEST:

Tamara Tran, Mayor

Annemarie Plaizier, City Recorder

CITY COUNCIL STAFF REPORT



MEETING DATE: February 15, 2024

TYPE OF ITEM: Work Items

PRESENTED BY: Josh Belnap

SUBJECT/AGENDA TITLE: Discussion on proposed Consolidated Fee Schedule Amendment related to development review fees

EXECUTIVE SUMMARY:

With last year's legislative changes regarding development review, staff began engaging with other cities and consultants representing smaller cities as we started identifying what Kaysville's code changes and development process would look like.

One item that was identified in this coordination was that cities have started implementing ways to assign the cost impacts for the review/coordination process to the developers creating the impact, rather than just being absorbed by the existing residents.

Staff has focused in on an option that would assign a fixed cost based on the number of units in a proposed development. That alleviates the cost burden experienced by the City, but also gives the developer a clear idea up front of what they can expect when planning their projects.

Staff would like to discuss the overall approach, hone in on what an applicable number would look like for Kaysville, and ultimately come back to council with an action item to amend the fee schedule.

With the recent focus on review time, and the potential for new developments approaching, we feel it is prudent to make this adjustment now, rather than waiting for the start of the new fiscal year.

City Council Options:

1) Move to action with recommendations, 2) Table

Staff Recommendation:

Move to Action

Fiscal Impact:

NA

ATTACHMENTS:

None

CITY COUNCIL STAFF REPORT



MEETING DATE: February 15, 2024

TYPE OF ITEM: Work Items

PRESENTED BY: Melinda Greenwood, Community Development Director

SUBJECT/AGENDA TITLE: Discussion on Kaysville City Center Community Reinvestment Area and the Redevelopment Agency Roles

EXECUTIVE SUMMARY:

City Staff has been working on creating a Community Reinvestment Area (CRA) since 2021. Staff last presented the concept of the Kaysville City Center Community Reinvestment Area to the City Council in September 2022. Since that time, staff has had several meetings with Davis County staff and Davis School District. Based on feedback from these two taxing entities, staff made revisions to the plan and presented a final draft to the Davis County Commission during a recent work session. The CRA plan was well received by the County Commission, so we are refreshing the Council on the proposed CRA Plan and updating the Council on the revised budget.

Several more steps will need to be completed before the CRA is established:

1. Interlocal agreements between the Redevelopment Agency of Kaysville City (RDA) and the taxing entities will need to be approved.
2. The RDA will need to post a public notice and hold a public hearing on the proposed plan and budget and then adopt both by resolution.
3. The City Council will need to adopt the plan by ordinance.
4. A 30-day protest period must be allowed.

We are hopeful the Kaysville City Center CRA will be approved as it will create opportunities to improve our City Center area.

City Council Options:

Discussion item.

Staff Recommendation:

N/A

Fiscal Impact:

The Kaysville City Center Community Reinvestment Area could create up to \$5.1M in revenue for the RDA to use within the project area.

ATTACHMENTS:

1. Kaysville Downtown Project Area Plan DRAFT 013024
 2. Kaysville Downtown CRA Budget DRAFT 013024
-



Kaysville City Redevelopment Agency
Kaysville City Center Reinvestment Area
***DRAFT* Project Area Plan**
January 30, 2024



I. Introduction	3
II. Recitals of Preconditions for Designating a Community Development Project Area	6
III. Definitions	7
IV. Project Area Boundaries [17C-5-105(1)]	8
V. General Statement of Land Uses, Layout of Principal Streets, Population Densities, Building Intensities and How They Will be Affected by the Project Area Development [17C-5-105(2)] ..	9
VI. Standards That Will Guide the Project Area Development [17C-5-105(3)]	10
A. General Design Objectives.....	10
B. Techniques to Achieve the Project Area Development Plan Objectives.....	12
C. Property Acquisition, Disposition and Development	12
1. Acquisition of Real Property	12
2. Cooperation with the Community and Public Entities.....	12
3. Property Management.....	13
4. Property Disposition and Development.....	13
5. Approvals	14
VII. How the Project Area Development Will Further Purposes of This Title [17C-5-105(4)] ..	14
A. Establishment of New Business	15
B. Creation of New Jobs	15
C. Public Infrastructure Improvements.....	15
D. Provision of Essential Services	16
VIII. The Plan is Consistent With and Will Conform to the Community's General Plan [17C-5-105(5)].....	16
IX. If Applicable, Describe How the Project Area Will Reduce or Eliminate Development Impediments [17C-5-105(6)]	16
X. Description of Any Specific Project or Projects That are the Object of the Proposed Community Reinvestment [17C-5-105(7)].....	16
XI. How Participants Will Be Selected [17C-5-105(8)].....	16
A. Selection of Private Developers	16
B. Identification of Developers Who are Currently Involved in the Proposed Community Reinvestment Area	17
1. Qualified Owners	17
2. Other Parties	17

3. Owner Participation Agreements	17
XII. Reasons for the Selection of the Community Reinvestment Project Area [17C-5-105(9)]	18
XIII. Description of the Physical, Social and Economic Conditions Existing in the Area [17C-5-105(10)].....	18
A. Physical Conditions.....	18
B. Social Conditions.....	18
C. Economic Conditions	18
XIV. Financial Assistance Anticipated to be Offered to a Participant [17C-5-105(11)]	18
XV. Results of the Public Benefit Analysis [17C-5-105(12)].....	19
XVI. If Applicable, State that the Agency Shall Comply with Section 9-8-404 [17C-5-105(13)]	22
XVII. State Whether the Plan is Subject to a Taxing Entity Committee or an Interlocal Agreement [17C-5-105(14)].....	22
Appendix A: Project Area Map.....	23
Appendix B: Legal Description	24
Appendix C: Kaysville Main Street Preferred Concept	26

KAYSVILLE CITY CENTER | CRA PROJECT AREA PLAN

I. INTRODUCTION

The Kaysville City Redevelopment Agency (“Agency”), following thorough consideration of the needs and desires of the City and its residents, as well as the need and capacity for redevelopment and new development, has carefully crafted this Kaysville City Center Community Reinvestment Project Area Plan (“Plan”).

In accordance with the terms of this Plan, the Agency will promote and provide for a variety of land uses, public improvements, infrastructure, redevelopment, and new development in an area focused in and around the historic downtown Kaysville, Main Street and 200 North. The Project Area includes approximately 261.5 acres (not including roads), with much of the study area currently developed with commercial uses. Only 40.4 acres (15.5%) of the proposed project area remain undeveloped.

On August 18, 2022, Kaysville City Council adopted the 2022 General Plan: The Next Chapter for Utah’s Hometown. The process was a comprehensive update and included a scientific survey of the community’s development preferences. In accordance with the adopted 2022 General Plan, the proposed Community Reinvestment Area (CRA) is intended to help carry out the vision as expressed by community members. An excerpt from the 2022 General Plan states:



Enrich our city center and downtown

We will enhance our city center with commercial and mixed-use development and investing in streetscape and parking.

A Guiding Principle of the 2022 General Plan is dedicated to Kaysville's City Center.

“The future city center will be a place that builds upon its history, while introducing new ideas and places to create a diverse and people-centric downtown center. The plan looks to enhance the city center with commercial and mixed-use development and invest in streetscape and parking. It will also focus on becoming a pedestrian-friendly district and a place for the community to gather for events and activities.”

The 2022 General Plan includes five objectives, one which is specifically centered on the downtown, or the city center. The objective states we will look to: Enrich our city center and downtown - We will enhance our city center with commercial and mixed-use development and investing in streetscape and parking.

In addition, the following 2022 General Plan Goals and Objectives support the creation of the Kaysville City Center Community Reinvestment Area and portrays the public’s interest in enriching the city center and downtown.

Chapter 1: Land Use & Placemaking Plan

- Objective 1.2: Preserve Historic Main Street as the heart of the community.
- Goal 2: Make Kaysville City Center Distinct and Identifiable from Adjacent Neighborhoods and Surrounding Cities.
- Objective 2.1: Improve commercial Frontage and streetscapes along key corridors such as Main Street and 200 North.
- Objective 2.2: Create a distinct city center and expand the “heart of the community” to include areas beyond the historic core.
- Objective 2.4: Create Places for the community to gather and events to draw users and visitors.
- Objective 9.1: Focus primary commercial uses in the City Center and secondary uses in smaller existing/future nodes.
- Objective 10.1: Encourage the development of a small commercial/civic Town Center near City Hall.



A bird's eye view looking north on Main Street from approximately 200 South.

Chapter 2: Transportation & Connectivity

- Objective 3.2: Use street design to shape neighborhood character.
- Goal 4: Improve access, walkability, and sense of place on Historic Main Street.
- Objective 4.2: Slow traffic.
- Objective 4.3: Develop shared parking solutions to support Main Street businesses and walkability.
- Objective 4.4: Improve Walkability.
- Objective 4.5: Improve cross and parallel streets to support needs of Main Street.
- Goal 5: Create Kaysville City Center to Increase Sustainable Transportation Choices.
- Objective 5.1: Create a new and enhanced person-focused network.
- Objective 5.3: Re-envision major corridors running through the area.

Chapter 5: Economic Development & Prosperity

- Goal 1: Promote Kaysville City Center Redevelopment to Strengthen Commercial Areas.
- Objective 1.2: Focus on small scale and local services to meet public requests and provide local growth.

- Goal 2: Utilize the wide variety of tools and incentives available to help achieve economic development goals.
- Objective 2.1: Establish redevelopment areas to fund infrastructure and future developments.
- Goal 3: Allow for Mixed Use Development in Identified Areas to Generate more Rooftops and Prevent Sales Leakage

In addition to these guidelines, goals and objectives, the City intends to further foster the following growth, development and redevelopment patterns in the Kaysville City Center CRA by:

- Promoting development that is high quality, diversified and adaptable to changing conditions
- Creating mixed-use areas where residents can enjoy a live/work lifestyle in addition to lively destinations
- Encouraging businesses and industries to locate and invest within the City in appropriate locations
- Implementing specific streetscape and mobility improvements to enhance pedestrian and transit centered transportation
- Creating districts and a places for residents to gather for community events and activities
- Refurbishing or replacing deteriorating structures so that land is used to its long-term potential

Through the aforementioned planning efforts, Kaysville City recognizes the impact new growth may have on quality of life characteristics. Current population projects Kaysville's population to reach 40,000-45,000 residents by 2030. According to the "Kaysville Main Street Vision," this growth will provide a benefit to the community by adding tax revenue. In addition, the increased population will provide new life to the downtown and increase visitors to Historic Main Street.

Kaysville's Historic Main Street started with mainly general merchandise stores from the mid-1860's until the Great Depression. Most buildings along Main Street are fairly old in terms of original construction date, and some buildings show signs of decline. The "Kaysville Main Street Vision" includes ideas that will transform Historic Main Street to be more walkable and embody Kaysville's identity and character to a higher degree.

In aggregate with the recent adoption of the 2022 General Plan, the City has made other giant strides to strengthen this request and support redevelopment in the downtown and city center area. Those efforts include:

- In fall of 2021, the City adopted its first mixed-use zoning ordinance which will help to facilitate a vibrant and active downtown and city center area. The ordinance was amended in 2023 to create additional opportunities for mixed-use development.
- In July of 2022, the City Council adopted a preferred alternative for the reconstruction of Main Street between 200 North and approximately 100 South. The City developed the preferred alternative after working closely with UDOT, Main Street businesses and property owners.
- In May of 2023, the City Council entered into an Exclusive Negotiation Agreement with Alchemy Development for redevelopment of the Old Library on the municipal block. The intention is to save the historic building and repurpose it for a food hall.
- In August of 2023, in efforts to assist with mixed-use projects and destination oriented development within the bulk of the City Center area, the City Council adopted an ordinance which prohibits uses which are singularly focused on vehicles.
- In December of 2023, the City submitted a grant application to Wasatch Front Regional Council for Transportation and Land Use Connection funds for a small area plan for the Kaysville City Center concept.
- Based on stakeholder feedback, the City conducted a circulation and parking analysis of the historic Main Street. A planned restriping project for spring of 2024 will add 45 additional on-street parking to area.

These projects have been intentionally completed prior to bringing the Kaysville City Center CRA to taxing entities so Kaysville City and the Agency could adequately show our commitment to the project.

It is the purpose of this Plan to clearly set forth the aims and objectives of this proposed CRA, its scope, its mechanism, and its value to the residents, businesses and property owners of the City and County. The Project is undertaken as a community reinvestment project pursuant to the provisions of the Act.

II. RECITALS OF PRECONDITIONS FOR DESIGNATING A COMMUNITY DEVELOPMENT PROJECT AREA

- A. Pursuant to the provisions of §17C-5-103 et seq. of the Limited Purpose Local Government Entities Community Development and Renewal Agencies Act, the governing body of the Redevelopment Agency of Kaysville City authorized the preparation of a draft community reinvestment Project Area plan; and
- B. Pursuant to the provisions of §17C-5-104(1)(a) and (b) of the Act, the City has a planning commission and general plan as required by law; and
- C. Pursuant to the provisions of §17C-5-104(3)(e) of the Act, the Agency has conducted one or more public hearings for the purpose of informing the public about the proposed

Project Area, allowing public comment on the draft Project Area Plan and whether the Plan should be revised, approved or rejected; and

- D. Pursuant to the provisions of §17C-5-104(3)(b) and (d) of the Act, the Agency made a draft Project Area Plan available to the public at the Agency's offices during normal business hours, provided notice of the Plan hearing and will hold a public hearing on the draft Plan on 2024 .

III. DEFINITIONS

As used in this Community Development Project Area Plan:


- A. The term "**Act**" shall mean and include the Limited Purpose Local Government Entities – Community Development and Renewal Agencies Act in Title 17C, Chapters 1 through 5, Utah Code Annotated 1953, as amended, or such other amendments as shall from time to time be enacted or any successor or replacement law or act.
- B. The term "**Agency**" shall mean the Kaysville City Redevelopment Agency, a separate body corporate and politic.
- C. The term "**base taxable value**" shall mean the base taxable value of the property within the Project Area from which tax increment will be collected, as shown upon the assessment roll last equalized, before: (A) the date the Project Area Plan is adopted by the City legislative body; and (B) the date the Agency adopts the first Project Area Budget.
- D. The term "**City**" shall mean Kaysville City, Utah.
- E. The term "**community**" shall mean the community of Kaysville City, Utah.
- F. The term "**community reinvestment**" shall mean development activities within the community, including the encouragement, promotion, or provision of development.
- G. The term "**developer**" shall mean the entities potentially investing in the development in the area.
- H. The term "**Plan Hearing**" means the public hearing on the draft Project Area Plan required under Subsection 17C-5-104 of the Act.
- I. The term "**planning commission**" shall mean the planning commission of the City.
- J. The term "**Project Area**" or "**Kaysville City Center Community Reinvestment Project Area**" shall mean the geographic area described in this Project Area Plan or Draft Project Area Plan where the community reinvestment set forth in this Project Area Plan or Draft Project Area Plan takes place or is proposed to take place.
- K. The term "**Project Area Budget**" shall mean a budget setting forth:
 - 1. The anticipated costs, including administrative costs, of implementing the Kaysville City Center Community Reinvestment Project Area Plan; and
 - 2. The tax increment, sales tax, and other revenue the Agency anticipates to fund the project.
- L. The term "**Project Area Map**" is the area depicted in Appendix A.

- M. The term **"Project Area Plan"** or **"Plan"** shall mean a Project Area plan adopted pursuant to the Act to guide and control community reinvestment activity within the Project Area.
- N. The term **"Kaysville City Center Community Reinvestment Project Area Plan"** or **"Plan"** shall mean a Project Area plan and Project Area map adopted pursuant to the Act to guide and control community reinvestment activities within a Project Area.
- O. The terms **"tax," "taxes," "property tax" or "property taxes"** include privilege tax and each levy on an ad valorem basis on tangible or intangible personal or real property.
- P. The term **"taxing entity"** shall mean a public entity that levies a tax on property within the Project Area.
- Q. The term **"Tax Increment"** shall mean the difference between the amount of property tax revenues generated each tax year by all Taxing Entities from the area designated in the Project Area Plan from which Tax Increment is to be collected, using the current assessed value of the property and the amount of property tax revenues that would be or were generated from that same area using the Base Taxable Value of the property.
- R. **All other terms** shall have the same meaning set forth in the Act unless the context clearly indicates otherwise.

IV. PROJECT AREA BOUNDARIES [17C-5-105(1)]

The Project Area consists of 261.5 acres located along Main Street, starting at approximately Mutton Hollow Road and continuing south to about 100 South. The Project area also covers the frontage area along 200 North starting near Main Street and continuing west under Interstate-15. The northwestern boundary follows Flint Street north until about Flint Meadow Drive. The Project area also includes the area directly southwest of the intersection of 200 North and Flint Street.

The Project Area boundaries and a Project Area map are included in Appendix A, with a legal description of the parcels in the Project Area included in Appendix B.



V. GENERAL STATEMENT OF LAND USES, LAYOUT OF PRINCIPAL STREETS, POPULATION DENSITIES, BUILDING INTENSITIES AND HOW THEY WILL BE AFFECTED BY THE PROJECT AREA DEVELOPMENT [17C-5-105(2)]

A. LAND USES IN THE PROJECT AREA

The existing land uses in the Project Area include primarily developed land (84.5%), with light industrial, commercial and residential dispersed throughout. Uses range from typical retail strip malls to flex warehouse, medical offices, vacant commercial and ranging densities of residential.

TABLE 1: LAND USE IN PROJECT AREA

Land Use	Acres	Percent of All Acres
Commercial	173.1	66.2%
Residential	48	18.35%
Vacant Land	40.4	15.45%
TOTAL	261.5	100%

Source: Davis County Assessor's Database, ZPFI

Land uses will be affected as currently vacant or underutilized land is developed in accordance with this Plan. The 40 acres of vacant land is planned for General Commercial or Mixed Use zoning. Redevelopment and development will change existing vacant land to commercial and mixed use projects. Other existing uses may experience use type changes as valuations and opportunities for redevelopment influence highest and best use considerations.

B. LAYOUT OF PRINCIPAL STREETS IN THE PROJECT AREA

The layout of principal streets in the Project Area is shown in Appendix A. Generally, major roads in the Project Area includes portions of 200 North, Main Street, Flint Street and I-15. Impacts to the layout of principal streets from this project area are not anticipated.

C. POPULATION DENSITIES IN THE PROJECT AREA

There are some areas of residential uses within the Project Area, including single-family homes, townhomes, and apartments of varying densities. Some proposed development in the Project Area may increase the number of homes, although specific densities are not known. Redevelopment of existing parcels will result in varied densities. It is estimated that the current population within the project area is 390 individuals, resulting in a total area population density of 1.5 persons per acre.


D. BUILDING INTENSITIES IN THE PROJECT AREA

The Project Area currently has a significant amount of commercial space located throughout the downtown. Current proposals for downtown, although still uncertain, suggest the possible addition of mixed-use projects, including more retail and commercial uses with residential to support the commercial uses.

VI. STANDARDS THAT WILL GUIDE THE PROJECT AREA DEVELOPMENT [17C-5-105(3)]

A. GENERAL DESIGN OBJECTIVES

Development within the Project Area will be held to high quality design and construction standards and will be subject to: (1) appropriate elements of the City's General Plan; (2) applicable City building codes and ordinances; (3) Planning Commission review and recommendation; (4) the City's land use code; (5) development agreements that include design guidelines or generally established guidelines; and (6) applicable small area plans.



Owners and developers will be allowed flexibility in the development of land located within the Project Area and are expected to obtain quality design and development. Development contemplated in the area should use materials that are in harmony with adjoining areas and subject to design review and approval by the City. It is envisioned that these design objectives will be codified or included in development agreements with prospective developers specifically addressing these points.

Coordinated, attractive and water wise landscaping will also contribute to the character of the Project Area. Construction materials including design pavers, retaining walls, fences, curbs, benches and other items will be addressed in the design guidelines.

Parking areas will be designed with careful regard to orderly arrangement, topography, relationship to view, ease of access, and as an integral part of the overall area function. Parking, and potentially shared parking agreements or new parking alignments for portions of the downtown area, will be a key consideration for redevelopment and new development.

All development will be accompanied by site plans, development data, and other appropriate materials clearly describing the development. These plans will also include land coverage, building setbacks, heights, landscaping, open space and any other data required by the City's land use code, development agreement or as requested by the City or the Agency.

The general standards that will guide development are those found in the Kaysville City General Plan. These include:

- Creating a large and varied grouping of uses to sustain civic and economic activity
- Interconnecting sites for pedestrian and vehicular access
- Renovation and preservation of historical landmarks, sites and structures

Additional consideration may be made for the following criteria:

- Strengthening the tax base and economic health of the entire community and the State of Utah.
- Implementing the tax increment financing provisions of the Act, which are incorporated herein by reference and made a part of this Plan.
- Encouraging economic use of new construction, redevelopment, or continued usage of existing properties located within the Project Area.
- Promoting and marketing the Project Area for Project Area development that would be complementary to existing businesses that would enhance the economic base of the City through diversification.
- Providing compatible relationships among land uses and quality standards for development, such that the area functions as a unified and viable center of community activity for the City.
- Removing any impediments to land disposition and development through assembly of land into reasonably sized and shaped parcels served by adequate public utilities and infrastructure improvements.
- Achieving an environment that reflects an appropriate level of concern for architectural, landscape and design principles, developed through encouragement, guidance, appropriate controls, and financial and professional assistance to owner participants and developers.
- Providing for construction of public streets, utilities, curbs and sidewalks, other public rights-of-way, streetlights, landscaped areas, public parking, water utilities, sewer utilities, storm drainage, open space, and other public improvements.
- Providing public streets and road access to the area to facilitate better traffic circulation and reduce traffic hazards by assisting in the street alignments.

B. TECHNIQUES TO ACHIEVE THE PROJECT AREA DEVELOPMENT PLAN OBJECTIVES

Activities contemplated in carrying out the Plan in the Project Area may include the acquisition and development of properties in the Project Area.

Parcels of real property located in the Project Area may be acquired by purchase, but may not be acquired by condemnation, unless from an Agency board member or officer with their consent [§17C-1-206 (1) and (2)(b)].

C. PROPERTY ACQUISITION, DISPOSITION AND DEVELOPMENT

The objectives of this Plan are to be accomplished by various means including but not limited to the following:

1. ACQUISITION OF REAL PROPERTY

The Agency may acquire, but is not required to acquire, real property located in the Project Area. The Agency may acquire property by negotiation, gift, devise, exchange, purchase, or other lawful method, but not by eminent domain (condemnation) unless from an Agency board member or officer with their consent.

The Agency is authorized to acquire any other interest in real property less than fee title such as leasehold interests, easements, rights of way, etc. by negotiation, gift, devise, exchange, purchase or other lawful method, but not by eminent domain (condemnation) unless from an Agency board member or officer with their consent [§17C-1-206 (1) and (2)(b)].

2. COOPERATION WITH THE COMMUNITY AND PUBLIC ENTITIES

The community and certain public entities are authorized by state law, with or without consideration, to assist and cooperate in the planning, undertaking, construction, or operation of projects within this Project Area. The Agency may seek the aid and cooperation of such public entities in order to accomplish the purposes of Project Area development and the highest public good.

The Agency, by law, is not authorized to acquire real property owned by a public entity without the consent of the public entity. The Agency, however, will seek the cooperation of all public entities that own or intend to acquire property in the Project Area. To the extent allowed by law, the Agency shall impose on all public entities owning real property in the Project Area the planning and design controls contained in this Plan to the end that uses and any future development by public entities will conform to the requirements of this Plan.

3. PROPERTY MANAGEMENT

During such time that property, if any, in the Project Area is owned by the Agency, such property shall be under the management and control of the Agency. Such property may be rented or leased by the Agency pending its disposition for Project Area development.

4. PROPERTY DISPOSITION AND DEVELOPMENT

The Agency is also authorized, by lawful means, to provide for and promote Project Area development of the Project Area as described below.

While there are currently a significant number of buildings or structures in the Project Area and it is relatively unlikely that there will ever be a need to demolish and clear a notable number of buildings or structures in the Area, the Agency is authorized to demolish and clear buildings, structures, and other improvements from any real property in the Project Area, should such a need occur, to carry out the purposes of this Plan.

The Agency is authorized to install and construct or to cause to be installed and constructed the public improvements, public facilities, and public utilities, within the Project Area, not prohibited by law which are necessary or desirable to carry out this Plan, as well as publicly-owned improvements and infrastructure outside the Project Area that are of benefit to the Project Area. The Agency is authorized to prepare or cause to be prepared as building sites any real property in the Project Area. The Agency is also authorized to rehabilitate or to cause to be rehabilitated any building or structure in the Project Area should such a need occur in the future. The Agency is also authorized to advise, encourage, and assist in the rehabilitation of property in the Project Area not owned by the Agency should such a need occur in the future.

For the purposes of this Plan, the Agency is authorized to sell, lease, exchange, subdivide, transfer, assign, pledge, encumber by mortgage or deed of trust, or otherwise dispose of any interest in real property. The Agency is authorized to dispose of real property by leases or sales by negotiation with or without public bidding. All real property acquired by the Agency in the Project Area shall be sold or leased to public or private persons or entities for development for the uses permitted in this Plan. Real property may be conveyed by the Agency to the City or any other public entity without charge. The Agency shall reserve such controls in the disposition and development documents as may be necessary to prevent transfer, retention, or use of property for speculative purposes and to ensure that development is carried out pursuant to this Plan. All purchasers or lessees of property from the Agency shall be made obligated to use the property for the purposes designated in this Plan, to begin and complete development of the property within a period of time which the Agency fixes as reasonable, and to comply with other conditions which the Agency deems necessary to carry out the purposes of this Plan.

To the maximum possible extent, the objectives of this Plan are to be accomplished through Agency encouragement of, and assistance to, private enterprise in carrying out development activities. To provide adequate safeguards to ensure that the provisions of this Plan will be carried out, all real property sold, leased, or conveyed by the Agency, as well as all property subject to participation agreements, shall be made subject to the provisions of this Plan by leases, deeds, contracts, agreements, declarations of restrictions, provisions of the City ordinances, conditional use permits, or other means. Where appropriate, as determined by the Agency, such documents or portions thereof shall be recorded in the Office of the County Recorder. The leases, deeds, contracts, agreements, and declarations of restrictions may contain restrictions, covenants, covenants running with the land, rights of reverter, conditions subsequent, equitable servitudes, or any other provision necessary or desirable to carry out this Plan.

To the extent now or hereafter permitted by law, the Agency is authorized to pay for, develop, or construct any building, facility, structure, or other improvement either within or outside the Project Area for itself or for any public entity to the extent that such improvement would be of benefit to the Project Area. During the period of development in the Project Area, the Agency shall require that the provisions of this Plan and of other documents formulated pursuant to this Plan are being observed, and that development in the Project Area is proceeding in accordance with development documents and time schedules. Plans for development by owners or developers shall be submitted to the City for review and approval. All Project Area development must conform to this Plan and all applicable federal, state, and local laws.

For the purpose of this Plan, the Agency is authorized to sell, lease, exchange, transfer, assign, pledge, encumber, and otherwise dispose of personal property.

5. APPROVALS

The City shall approve the design of all development within the Project Area to ensure that development therein is consistent with this Plan. Mixed Use development projects or increment funded projects will need approval from the City Council and/or the Agency.

VII. HOW THE PROJECT AREA DEVELOPMENT WILL FURTHER PURPOSES OF THIS TITLE [17C-5-105(4)]

It is the intent of the Agency, with the assistance and participation of private owners, to facilitate new development or redevelopment within the Project Area that includes the objectives previously stated that are a key part of the Kaysville City 2022 General Plan. The proposed Project Area will additionally provide for the encouragement, promotion, or provision of a walkable historic downtown in the community. Further, the Project will strengthen the tax base of the community, will accomplish community development objectives, and create a well-planned and vibrant downtown core. The Project Area Plan will further the purposes of the Act by accomplishing the following items:

A. ESTABLISHMENT OF NEW BUSINESS

The Project Area includes the potential for notable commercial development which will benefit the State and the City through increased job creation, increased sales tax base, and increased income taxes paid.

B. CREATION OF NEW JOBS

The Project Area includes the potential for new businesses and related jobs. It is anticipated that new jobs will be created as new businesses are attracted to the revitalized downtown and city center areas.

1. **Office** – There are current plans for the addition of 56,000 square feet of office space in the project area. Staff estimates another 54,000 square feet of office could be added to the project area over its 15 year course. Current market conditions indicate one job is created per 200 square feet of office space. If current plans and estimates are realized, the Kaysville City Center CRA could bring more than 550 new office jobs to the Project Area.
2. **Commercial** – Commercial jobs include retail sales and services, restaurants, banks and other similar uses. Current market conditions indicate one job is created for every 150 square feet of commercial space. Conservative estimates for new commercial space within the Project Area include the addition of 45,000 square feet of new commercial space which would create at least 300 new jobs.
3. **Construction** – Temporary construction jobs will also be created within the project area. It is not feasible at this time to estimate how many jobs will be created throughout the 15 year time period.

C. PUBLIC INFRASTRUCTURE IMPROVEMENTS

The construction of the public infrastructure improvements and upgrades necessary to the area will support a variety of development and will provide for future development in surrounding areas. Infrastructure is an important element of economic development and areas that lack good infrastructure are not able to be competitive in attracting good-quality businesses to locate in their community.

The development of the Project Area and the associated public infrastructure improvements will also: (1) make the land within the Project Area more desirable and potentially more accessible to and from other parts of the City; and (2) allow existing infrastructure to be extended and connected to other infrastructure and thereby used more efficiently. Thus, the components of the Project provided in this Plan will encourage,

promote, and provide for community development within the Project Area and the City generally for years to come.

D. PROVISION OF ESSENTIAL SERVICES


Potential redevelopment or new development will most likely provide essential services to existing and possible new housing units for the Project Area. Commercial development will also likely include office spaces which may offer a variety of medical and dental services as well as professional office uses.

VIII. THE PLAN IS CONSISTENT WITH AND WILL CONFORM TO THE COMMUNITY'S GENERAL PLAN [17C-5-105(5)]

The City Center Project Area Plan is consistent with the City's 2022 General Plan. New development or redevelopment will diversify and strengthen the City by adding updated or new uses to the community.

Further development of this area will provide a strong tax base that will enable the City to expand and provide additional services.

For more details regarding the Kaysville City Center CRA and how the 2022 General Plan supports this request, please refer to Section I: Introduction.



IX. IF APPLICABLE, DESCRIBE HOW THE PROJECT AREA WILL REDUCE OR ELIMINATE DEVELOPMENT IMPEDIMENTS [17C-5-105(6)]

While some portions of the study area may have development impediments (largely due to age), these are relatively minimal and not overly applicable to the Project Area plan.

X. DESCRIPTION OF ANY SPECIFIC PROJECT OR PROJECTS THAT ARE THE OBJECT OF THE PROPOSED COMMUNITY REINVESTMENT [17C-5-105(7)]

The Project Area is intended to accomplish a larger vision of the historic Main Street downtown and Kaysville City Center Concept and is not intended for any specific development. It is assumed that multiple parts of the study area will support new development or redevelopment, resulting in new residential units, retail offerings, and commercial uses (office and flex office).

XI. HOW PARTICIPANTS WILL BE SELECTED [17C-5-105(8)]

A. SELECTION OF PRIVATE DEVELOPERS

The Agency contemplates that owners of real property within the Project Area may take advantage of the opportunity to develop their property, redevelop, maintain, or sell their

property to developers for the development of facilities within the Project Area. In the event that owners do not wish to participate in the development in compliance with the Plan, or in a manner acceptable to the Agency, or are unable or unwilling to appropriately participate, the Agency reserves the right pursuant to the provisions of the Act to acquire parcels, to encourage other owners to acquire other property within the Project Area, or to select non-owner developers by private negotiation, public advertisement, bidding or the solicitation of written proposals, or a combination of one or more of the above methods. It is assumed that a moderate number properties in the area will not be the subject of new development or significant redevelopment but will ultimately benefit from the goals and implementation of the plan.

B. IDENTIFICATION OF DEVELOPERS WHO ARE CURRENTLY INVOLVED IN THE PROPOSED COMMUNITY REINVESTMENT AREA

There are no developers who are currently pursuing the use of tax increment financing in the proposed Kaysville City Center Community Reinvestment Area. Development guidelines and agreements regarding the use and payment of tax increment will be set forth in Development Agreement or other agreements between the Agency and any development teams.

1. QUALIFIED OWNERS

Any person wishing to become a developer will be required to own or have the right to purchase a part of the Project Area.

2. OTHER PARTIES

If there are no owners in the Project Area who possesses the skill, experience, and financial resources necessary to become a developer in the Project Area or are able to become a developer to part of the Project Area, the Agency may identify other qualified persons who may be interested in developing part of the Project Area. Potential developers may be identified by one or more of the following processes: (1) public solicitation, (2) requests for proposals (RFP), (3) requests for bids (RFB), (4) private negotiation, or (5) some other method of identification approved by the Agency.

3. OWNER PARTICIPATION AGREEMENTS

The Agency has not entered into nor does it intend to enter into any owner participation agreements or agreements with developers to develop parts of the Project Area until after the Agency and the City decide whether or not to adopt this Plan for the Project Area.

XII. REASONS FOR THE SELECTION OF THE COMMUNITY REINVESTMENT PROJECT AREA [17C-5-105(9)]

The Project Area was selected by the Agency as having a significant impact to the community and a near-term ability to strengthen Kaysville City and Davis County by allowing for appropriate redevelopment or new development of commercial space, residential housing, and public infrastructure that may support future development anticipated for Kaysville City and provide for development in surrounding areas.

Specific boundaries of the Project Area were arrived at by the Agency after a review of the area by members of the Agency, City staff, economic development consultants, and other technical and legal consultants. Planned treatment of this area is intended to stimulate development to the degree necessary for sound long-term growth in the Project Area and to encourage the development of real property located within the Project Area. Finally, the Project Area is a key element in the City's 2022 General Plan.

XIII. DESCRIPTION OF THE PHYSICAL, SOCIAL AND ECONOMIC CONDITIONS EXISTING IN THE AREA [17C-5-105(10)]**A. PHYSICAL CONDITIONS**

The Project Area consists of approximately 261.5 acres of land as shown on the Project Area map located in the Addenda.

B. SOCIAL CONDITIONS

There are currently a significant number of buildings of nearly all use types within the Project Area. No unusual social conditions were found to exist. The Project Area Plan may help to further bring consumers and visitors from across the area to the Project Area for shopping, living, and employment.

C. ECONOMIC CONDITIONS

The study area currently generates a significant amount of taxable values from its variety of uses. Overall, as of the most recent tax year (2023), the project year had a base taxable value of \$203,550,124.

XIV. FINANCIAL ASSISTANCE ANTICIPATED TO BE OFFERED TO A PARTICIPANT [17C-5-105(11)]

The Agency intends to negotiate and enter into one or more inter-local agreements with Davis County, Davis County School District, Weber Basin Water Conservancy District, Davis County Mosquito Abatement District, Central Davis County Sewer District, Davis County Library, and Kaysville City to secure receipt of a portion of the property tax increment generated within the Project Area that would otherwise be paid to those taxing entities. Collectively, those tax revenues may be used for the reasons already outlined. Subject to the provisions of the Act, the Agency may agree to pay for eligible development costs and

other items from such tax revenues for any period of time the Agency and the taxing entities may deem appropriate under the circumstances.

XV. RESULTS OF THE PUBLIC BENEFIT ANALYSIS [17C-5-105(12)]

A. THE BENEFIT OF ANY FINANCIAL ASSISTANCE OR OTHER PUBLIC SUBSIDY PROPOSED TO BE PROVIDED BY THE AGENCY

1. AN EVALUATION OF THE REASONABLENESS OF THE COSTS OF THE PROPOSED PROJECT AREA DEVELOPMENT

The preliminary cost estimates for downtown improvements include expenses for roadways, parking improvements, public open space areas, façade programs, trail development, etc., and appear to be reasonable given current and anticipated market conditions.

The City has partnered with UDOT to create a specific concept plans for rehabilitation of Main Street between 200 North and approximately 100 South. A copy of the Main Street Preferred Alternative (Appendix C) which was adopted by the City Council on July 21, 2022 included a cost estimate of \$2,363,000 (2025 valuation).

Estimates of costs and probable project area use for increment include:

- Main Street improvements between 200 North and 100 South, including expansion, installation of medians, intersection realignment, and traffic calming (~\$2,363,000)
- Other roadway and intersection improvements (~\$800,000)
- Beautification and landscaping (~\$250,000)
- Sidewalk expansion or realignment, trail development, etc. (~\$500,000)
- Creation of pedestrian oriented atmosphere and facilities (~\$250,000)
- Creation of public open space amenities (~\$190,000)
- Property acquisition (~\$2,000,000)
- Parking enhancements, parking structure and facilities (~\$5,000,000)
- Traffic, circulation and parking studies (~\$35,000)
- Relocation assistance for businesses and or residences (~\$350,000)
- Location assistances for businesses (~\$150,000)
- Demolition and pre-demolition environmental assessment costs (~\$20,000)
- Utility expansion, extension or upgrades (~\$250,000)
- Installation of fiber optic networks (~\$200,000)

- Facilitation of façade grant and loan programs (~\$200,000)
- Relocation of historical markers (~\$75,000)

2. EFFORTS TO MAXIMIZE PRIVATE INVESTMENT

The City has made efforts to maximize private investment in the area. The City has pursued a development pattern that will attract desirable tenants and will bring a strong tax base to the City. The City anticipates that this Project Area focus will create new jobs. The wages paid for these jobs will then be re-spent, by the private sector, in the local and regional economies that will bring benefits to private businesses in the area.

It is likely that redevelopment and new development will significantly increase taxable values from the current taxable value of around \$203,550,124, to roughly \$280,061,524 over 15 years. The Project Area is currently generating approximately \$1,981,968 in property tax revenues; it is projected to generate roughly \$2,606,362 net present value (NPV) per year at the end of 15 years. Developers will also likely be paying for improvements to various public infrastructure needs.

3. RATIONALE FOR USE OF PROJECT AREA FUNDS

Tax increment funds are necessary in order for this site to be competitive with similar sites under consideration. Building upgrades and enhancements need to be made to those showing signs of aging and deterioration. Therefore, in order to enhance this area and uplift the desirability of the city center core, the Agency is proactively seeking to create a Project Area, with the use of tax increment, so that redevelopment and new development can be considered.

4. ESTIMATE OF TOTAL PROJECT AREA FUNDS AND LENGTH OF TIME OF PROJECT AREA

Project Area funds will be disbursed to the Agency for a period of 15 years and are anticipated to be approximately \$5,173,451 over the 15-year period, with a NPV of nearly \$3,301,171.

B. THE ANTICIPATED PUBLIC BENEFIT DERIVED FROM THE PROPOSED PROJECT AREA DEVELOPMENT

1. BENEFICIAL INFLUENCES ON THE COMMUNITY'S TAX BASE

The property tax base of the taxing entities should increase by over \$76,000,000 from the various investments in real property (land and buildings) alone. In addition, the personal property tax base of the taxing entities will increase but will vary depending on the type of equipment located in the Project Area as well as individual depreciation schedules.

In addition to tax revenues, the Project Area will generate other revenues including sales tax, Class B/C Road Funds, business license fees, charges for services, and one-time fees such as building permits and impact fees.

2. ASSOCIATED BUSINESS AND ECONOMIC ACTIVITY STIMULATED BY THE DEVELOPMENT

Other business and economic activity likely to be stimulated includes business employee and construction expenditures. There are significant opportunities for increased economic development and tax generating development that can occur within the immediate sphere of influence of the Project Area that otherwise may not occur in a timely basis or at the same level of increased development and private investment.

3. BUSINESS AND EMPLOYEE EXPENDITURES

It is anticipated that employees and business owners in the Project Area will directly or indirectly purchase local goods and services related to their operations from local or regional suppliers. These purchases will likely increase employment opportunities in the related areas of business equipment, furniture and furnishings, business supplies, computer equipment, communication, security, transportation and delivery services, maintenance, repair and janitorial services, packaging supplies, office and printing services, transportation and delivery services.

A summary of benefits is as follows:

- Provide an increase in direct purchases in the City and the County.
- Provide economic diversification within the City and the County.
- Complement existing businesses and industries located within the City by providing new employees who may live and shop and pay taxes in the City and the region.
- Generate indirect and induced (“multiplier”) impacts from business and employee expenses in the local area. The types of expenditures by employees in the area will likely include shopping for personal and household goods, lunches at area restaurants, convenience purchases and personal services (haircuts, banking, dry cleaning, etc.). The employees will not make all of their convenience or personal services purchases near their workplace, and each employee's purchasing patterns will be different. However, it is reasonable to assume that a percentage of these annual purchases will occur within close proximity to the workplace (assuming the services are available).

4. CONSTRUCTION EXPENDITURES

Economic activity associated with the development will include construction activity. Construction costs for labor and materials will likely be notable. This will create a moderate number of construction jobs. Construction supplies are also anticipated to create significant sales tax revenues for the State, County and City.

5. ADOPTION OF THE PLAN IS NECESSARY AND APPROPRIATE TO UNDERTAKE THE PROJECT AREA PLAN

Adoption of the Plan is necessary and appropriate to undertake the Project Area Plan because:

- The Plan conforms with and furthers the City's General Plan; and
- Private investment will increase the tax base by over \$76,000,000 which will provide increased tax revenues to all taxing entities.

XVI. IF APPLICABLE, STATE THAT THE AGENCY SHALL COMPLY WITH SECTION 9-8-404 [17C-5-105(13)]

The Agency will comply with Section 9-8-404 if any of the existing buildings are eligible for inclusion in the National Register of Historic Places or the State Register and the Agency spends Agency funds on the demolition or rehabilitation of said existing buildings.

XVII. STATE WHETHER THE PLAN IS SUBJECT TO A TAXING ENTITY COMMITTEE OR AN INTERLOCAL AGREEMENT [17C-5-105(14)]


This Plan was not adopted before May 14, 2019, as stated in the code, however, this Plan is subject to Interlocal Agreements.

APPENDIX A: PROJECT AREA MAP

Kaysville CRA Boundary and Parcels

Legend

-  Proposed CRA Boundary
 Kaysville CRA Parcels



APPENDIX B: LEGAL DESCRIPTION

CRA Metes and Bounds description (**Description Only – NOT SURVEYED**)

Commencing at the NW Corner of Section 33, Township 4 North, Range 1 West and running S 0 degrees 37'28" W 513.12 feet along the section boundary; thence N 89 degrees 52'23" E 521.92 feet to the True Point of Beginning; thence continue N 54 degrees 54'11" E 1346.71 feet; thence continue S 21 degrees 14'27" E 317.12 feet; thence continue S 69 degrees 32'05" W 215.99 feet; thence continue S 20 degrees 26'27" E 430.41 feet; thence continue S 69 degrees 33'59" W 485.95 feet; thence continue S 22 degrees 01'30" E 355.05 feet; thence continue S 69 degrees 33'25" W 206.34 feet; thence continue S 22 degrees 17'45" E 571.30 feet; thence continue S 67 degrees 34'09" W 24.29 feet; thence continue S 00 degrees 20'39" W 187.85 feet; thence continue S 21 degrees 56'42" E 457.92 feet; thence continue N 67 degrees 20'02" E 656.17 feet; thence continue S 24 degrees 16'23" E 218.83 feet; thence continue S 01 degrees 31'40" W 465.02 feet; thence continue S 88 degrees 28'34" E 1125.89 feet; thence continue N 01 degrees 42'10" E 238.06 feet; thence continue S 88 degrees 30'16" E 532.81 feet; thence continue N 02 degrees 19'43" E 285.07 feet; thence continue S 88 degrees 34'04" E 250.81 feet; thence continue N 24 degrees 52'50" W 2360.1 feet; thence continue N 89 degrees 45'24" E 350.76; thence continue S 24 degrees 57'41" E 158.01 feet; thence continue N 83 degrees 06'09" E 1125.78 feet; thence continue S 47 degrees 51'21" E 147.92 feet; thence continue N 43 degrees 16'16" E 419.70 feet; thence continue S 48 degrees 48'26" E 628.01 feet; thence continue S 47 degrees 23'18" W 230.72 feet; thence continue S 48 degrees 09'53" E 581.23 feet; thence continue N 47 degrees 47'11" E 104.89 feet; thence continue S 44 degrees 21'00" E 510.69 feet; thence continue S 86 degrees 36'28" E 58.3 feet; thence continue N 54 degrees 03'43" E 94.62 feet; thence continue S 65 degrees 24'48" E 84.65 feet; thence continue N 69 degrees 11'29" E 118.45 feet; thence continue S 38 degrees 59'04" E 126.89 feet; thence continue S 63 degrees 26'20" W 143.79 feet; thence continue S 58 degrees 58'22" E 89.92 feet; thence continue S 28 degrees 30'46" W 47.95 feet; thence continue S 74 degrees 38'39" E 340.22 feet; thence continue N 20 degrees 35'51" E 501.5 feet; thence continue S 42 degrees 37'03" E 750.1 feet; thence continue N 44 degrees 02'30" E 267.13 feet; thence continue S 42 degrees 30'20" E 178.45 feet; thence continue S 47 degrees 16'39" W 52.19 feet; thence continue S 41 degrees 23'20" E 290.64 feet; thence continue S 30 degrees 03'56" W 80.98 feet; thence continue S 46 degrees 04'20" E 288.76 feet; thence continue N 58 degrees 35'44" E 25.44 feet; thence continue S 31 degrees 57'55" E 315.08 feet; thence continue S 18 degrees 01'49" E 210.07 feet; thence continue N 74 degrees 44'18" E 132.54 feet; thence continue S 24 degrees 00'18" E 83.56 feet; thence continue S 08 degrees 06'21" E 142.44 feet; thence continue S 35 degrees 57'02" W 60.54 feet; thence continue S 00 degrees 44'49" W 201.24 feet; thence continue N 89 degrees 15'00" E 342.25 feet; thence continue S 01 degrees 14'24" W 1799.83 feet; thence continue N 89 degrees 02'59" W 843.92 feet; thence continue N 0 degrees 25'53" E 132.57 feet; thence continue N 35 degrees 27'07" E 43.14 feet; thence continue N 89 degrees 49'43" E 49.05 feet; thence continue N 0 degrees 20'02" E 133.65 feet;

thence continue N 89 degrees 39'20" W 24.99 feet; thence continue N 0 degrees 19'14" E 113.73 feet; thence continue N 07 degrees 57'23" W 20.23 feet; thence continue N 89 degrees 39'21" W 54.99 feet; thence continue N 0 degrees 20'40" E 110.98 feet; thence continue N 0 degrees 34'59" W 64.42 feet; thence continue S 88 degrees 11'46" E 83.87 feet; thence continue N 1 degrees 03'18" E 381.9 feet; thence continue N 88 degrees 54'34" W 10.38 feet; thence continue N 0 degrees 40'54" E 196.94 feet; thence continue N 89 degrees 16'21" W 149.42 feet; thence continue N 0 degrees 57'52" E 189.03 feet; thence continue S 89 degrees 07'39" E 99.94 feet; thence continue S 89 degrees 09'56" E 15.97 feet; thence continue N 0 degrees 21'13" E 69.63 feet; thence continue N 89 degrees 09'09" W 2190.82 feet; thence continue N 0 degrees 57'57" E 332.87 feet; thence continue N 89 degrees 22'48" W 1511.4 feet; thence continue S 08 degrees 06'15" E 51.55 feet; thence continue S 26 degrees 47'17" E 135.21 feet; thence continue S 46 degrees 03'27" W 133.78 feet; thence continue N 25 degrees 05'25" W 192.2 feet; thence continue S 64 degrees 13'55" W 140.41 feet; thence continue S 75 degrees 12'08" W 210.27 feet; thence continue N 39 degrees 23'08" W 76.81 feet; thence continue N 17 degrees 34'21" W 102.01 feet; thence continue N 88 degrees 33'08" W 38.08 feet; thence continue S 17 degrees 34'21" E 92.04 feet; thence continue S 55 degrees 40'56" W 123.56 feet; thence continue N 33 degrees 53'57" W 24.08 feet; thence continue N 88 degrees 32'35" W 240.02 feet; thence continue N 01 degrees 31'41" E 48.94 feet; thence continue N 89 degrees 42'44" W 704.71 feet; thence continue S 01 degrees 31'39" W 44.99 feet; thence continue N 88 degrees 28'36" W 434.95 feet; thence continue S 54 degrees 59'23" W 64.81 feet; thence continue S 18 degrees 39'09" W 114.27 feet; thence continue N 38 degrees 42'09" W 120.33 feet; thence continue S 44 degrees 48'14" W 91.03 feet; thence continue N 35 degrees 34'47" W 136.05 feet; thence continue S 51 degrees 49'40" W 224.26 feet; thence continue S 63 degrees 49'31" W 285.46 feet; thence continue S 20 degrees 59'09" E 69.01 feet; thence continue S 55 degrees 57'02" W 521.65 feet; thence continue N 32 degrees 37'16" W 991.73 feet; thence continue S 89 degrees 35'48" E 748.82 feet; thence continue N 23 degrees 21'29" W along said line 2370.43 feet to the Point of Beginning.

APPENDIX C: KAYSVILLE MAIN STREET PREFERRED CONCEPT

Kaysville Main Street DRAFT Preferred Concept

This document summarizes the preferred concept for Kaysville's Main Street (S.R. 273). This is a joint vision created by both Kaysville City and the Utah Department of Transportation. The concept was developed through a collaborative process involving key people in UDOT and Kaysville and addresses the needs of both UDOT and the Kaysville community.


The concept builds on Kaysville City's Main Street Vision the City created in 2019. This vision is a broad directive for Main Street, and this more detailed collaboration with UDOT for the street right-of-way and transportation elements is an important implementation piece of that vision.

The initial conversations among Kaysville and UDOT highlighted two key priorities: placemaking and access. The concept reflects these themes. Place in this case means public space, aesthetics, slowing traffic, and a full downtown streetscape extension. Access means pedestrian crossings, parking, access management, network, and active transportation.

This document provides an overview of the concept and its elements; the details and examples of each element; and ideas for how the project will be implemented and funded.



Rendering of Kaysville Main Street Preferred Concept



PEDESTRIAN



New pedestrian space



Marked pedestrian crossing



HAWK pedestrian-activated crossing

STREETSCAPE



Street trees



Planted median island

PARKING



Reconfigured diagonal parking



Reconfigured parallel parking



Key district off-street parking area

NETWORK LINKS



Shared use pathway

Concept Overview

The Kaysville Main Street Preferred Concept seeks to improve Main Street's access and sense of place while still moving traffic on the state highway corridor. It does this through a major extension of the pedestrian area on the west side of the central block of Main Street and landscape and streetscape improvements in the new space; a lateral transition of the traffic lanes to the east to allow for the west side sidewalk extension; a set of landscaped medians; the movement of the existing HAWK to a mid-block location and additional pedestrian crossings at Center Street and 100 North; reconfiguring of 100 North and Center Street with diagonal parking; and some restriction of turns on and off Main Street. The concept keeps the street's existing vehicle capacity.

These improvements will create more high quality public space; improve the pedestrian environment; slow traffic; increase the ability for pedestrians to cross the street safely, conveniently, and with ease; better connect Main Street to the parking on the City Hall block; maintain parking and make it overall more convenient; and manage vehicle access on and off Main Street.

The major tradeoff of the concept is likely the loss of on-street parking spaces on Main Street (primarily on the east side) in exchange for a much bigger pedestrian environment on the west side of the street, a more traffic calmed environment, and shorter and more frequent pedestrian crossings. The concept seeks to make the parking in the City Hall block more convenient to Main Street patrons and diagonal spaces on the nearby cross streets help make up for lost Main Street parking as well.

Concept Elements

CENTRAL BLOCK

- ➊ Move HAWK signal and crosswalk from Center Street to mid-block between Center Street and 100 North
- ➋ Extend curb on west side in central block of Historic Main Street
- ➌ Preserve the majority of on-street parking on west side of central block with time-restricted or pay spaces - with the exception of the north and south ends and middle, where pedestrian area curb extensions would take the place of an estimated six spaces.
- ➍ Lane shift to east so that travel lanes are against existing east curb in central block; begin shift on north and south blocks
- ➎ Median in central block with pedestrian refuges at mid-block, 100 North and Center Street, and "super street" access management extension
- ➏ Stripe diagonal parking on one side of Center Street and 100 North (with parallel on the other side)
- ➐ East side shared use path to connect with other planned pathways, especially to the south
- ➑ Intuitive, direct pathway through the civic block, linking Main Street to the parking lot and beyond to the Recreation Center and Senior Center and Kaysville Elementary, with supportive wayfinding to parking and downtown locations
- ➒ Curb extensions into cross streets at the corners of Center Street and 100 South, similar to the existing curb extensions at Center Street on west side of Main Street

NORTH AND SOUTH BLOCKS

- ➓ Downtown streetscape extension to north and south blocks
- ➑ Sidewalk extensions into shoulder at north and south ends of historic Main Street
- ➒ Short medians at strategic locations on north and south blocks
- ➓ Marked pedestrian crossing with ped refuge on north leg of 50 West crosswalk – change signal phases accordingly

Enhancing public space.

The concept starts with public space – leveraging and complementing Kaysville’s historic storefronts and civic buildings with a wide, high-quality sidewalk area and pedestrian realm that will provide space for strolling, people-watching, outdoor dining, farmer’s markets and events.

This space is created by extending the west side sidewalk substantially at the central block to a 20- to 30-foot pedestrian realm with street trees, landscape and furnishings such as benches and pedestrian scale lighting, as well as opportunities for outdoor dining. This space can be a large piece of revitalizing Main Street, complementing existing businesses and attracting new ones, especially restaurants. Most importantly, it can be a promenade for the community to gather, whether for events such as farmers markets or parades or on a typical Saturday evening.

The possibility remains for upgrades on the east side of Main Street with enhancements to the plaza area near the former library building. This could be a space that connects to and complements the widened pedestrian realm on the west side. Plaza upgrades and could host events such as a Christmas tree lighting.

Traffic calming.

Calming traffic is a foundational part of a vibrant Main Street and walkable downtown. The Kaysville Main Street concept has several elements that will contribute to traffic slowing, while not causing undue delays. With the curb extension and the median, the concept narrows the roadway. It creates a human scale for the street with trees, streetscape, and public space on the sides. And the lanes moving to the east edge of the roadway at the central block creates a lateral shift that drivers must make, which will also slow them down.

Increasing and improving pedestrian crossings.


Moving the HAWK crosswalk currently located at Center Street to mid-block will place a safe crossing at the most desired point along Main Street. This will work hand-in-hand with the parking strategy by connecting to and promoting where people can park in the middle of the block in place of some of the removed parking along the west side storefronts.

In addition, because of the traffic calming strategies, the shortening and breaking up of the crossing by the curb extension and the pedestrian refuge, crossings will be marked at 100 North and Center, providing a frequent series of crossings in the heart of Main Street that will also work with traffic patterns.

Finally, the extension of downtown streetscape and pedestrian realm includes the addition of the north crosswalk leg of the Main Street / 50 West signalized



Above are examples of the type of wide pedestrian realm that the concept proposes for Kaysville Main Street’s central block, demonstrating a range of uses, including strolling, dining, landscape, and public space.



A center median in a downtown area can provide multiple functions - establishing a pedestrian refuge for pedestrian crossings while calming traffic, managing access, and greening the street, such as in this example from downtown Salt Lake City.

intersection, which will also be a bike/multi-use path crossing.

Increasing aesthetics/beautification.

Aesthetics are a major part of the concept. The aesthetics play off the historic character of Main Street's storefronts, civic buildings, and large trees. Aesthetics have two key aspects in this concept:

- Greening through additional street trees and other landscape – both along the sidewalk and in the new medians, which will be planted with trees and other landscape (while maintaining appropriate sight distances).
- Streetscape elements that complement and reflect the heritage of Kaysville and the historic character of Main Street.

Reconfiguring and connecting parking.

Parking is a critical issue on most Main Streets, and because of the Main Street Vision's emphasis on vehicular and pedestrian access to Main Street, parking takes on extra importance. The concept's approach to parking is to designate on- and off-street parking resources that complement the public space approach and support the desired uses of Main Street. While some of these changes may be surprising and unsettling to the community initially, we think this parking approach in the long term will best achieve the Vision. The concept's parking related recommendations are:

- Remove on-street parking on the east side of Main Street's central block, preserving all but an estimated six spaces on the west side, and making these on-street spaces short-term parking intended for customers.
- Replace these Main Street on-street parking spaces by creating diagonal parking on one side of 100 North and the east segment of Center Street (the west segment is already diagonal on one side). Creating these parking areas is still convenient to Main Street storefronts.
- Having a pedestrian-activated HAWK signal mid-block, a pedestrian refuge, and slowed traffic much more closely links the west side storefronts to the civic block parking lot.



A coordinated set of streetscape amenities is important to create a human scale environment on Main Street.



The approach to Center Street of diagonal parking on one side can be expanded to the other side of Main Street and 100 North.

- The civic lot and other parking would benefit from increased wayfinding and information for visitors.

Managing vehicle access.

Access management is a key part of the Main Street concept. Restricting some turn and through-traffic movements reduces potential conflicts and allows for safer pedestrian circulation.

- Turn restrictions: The “super street” concept will help reduce conflicts from left and through movements from 100 North.

Connecting the street/pathway network


While the gridded street network of Kaysville’s downtown area is established, one smaller street/pathway network improvements is recommended: the consideration of a more intuitive pathway through the civic block, linking the planned mid-block crosswalk of Main Street to the parking lot and the recreation center, and then to Kaysville Elementary School beyond.

Extending the downtown street character

The north and south blocks of Kaysville’s Main Street have parts of the historic streetscape treatments, such as street trees, but also have more of a suburban character, with unbuffered parking lots, frequent driveways, and grassy park strips. The concept includes the extension of the central block streetscape features that evoke a walkable downtown to the north and south blocks, as well as sidewalk extensions into the shoulder at the north and south entries into the downtown and



An example of the “super street ” concept that restricts left and though movements from cross streets onto a major street.



Downtown Salt Lake City has a range of positive examples of pedestrian pathways through the district's large blocks that inform a potential pathway through Kaysville's civic block.

landscaped medians that still allow for left turns into driveways.

Helping people riding bikes access Main Street.

While the focus of the Main Street concept is pedestrian and vehicular access, there are opportunities to better connect people riding bikes to Main Street. The best opportunity for this concept is to manifest an extension of the “Ponds” multi-use path up 50 West to Main Street and build a multi-use pathway on the east side of Main Street. This emphasis on bike and pedestrian mobility on the east side of Main Street complements the emphasis on the west side of public space.

This shared use path does present some implementation challenges. There is little existing right-of-way above the curb to transform into a multi-use path, which should be at least 8 feet wide, preferably 10 feet. While the east side of the central block of Main Street does include City-owned property, this space includes mature trees and relatively new investments in landscaping and the police station stairs. Consequently,



While the Kaysville Main Street Vision focuses on pedestrian and vehicle access, bicycles are a relatively popular way for people to access Main Street. This composite image of all non-vehicle trips in one hour on Main Street is heavily tilted toward people riding bikes or scooters.

Concept Development Process

The Kaysville Main Street concept builds on the City's Main Street Vision created in 2019. At the same time, the City was developing an updated General Plan, whose process identified Main Street as a priority. This created the opportunity to initiate a focused collaboration with the Utah Department of Transportation (UDOT) on how improvements to the Main Street right-of-way can help support the City's vision.


The process started in February 2021 with a site tour undertaken by Kaysville City leadership and staff and UDOT Region 1 staff. Then, over an online meeting using a polling program, the same group provided feedback 1) about the importance of a range of potential goals and 2) what each goal means. These conversations highlighted two key shared priorities: **placemaking**- public space, aesthetics, slowing traffic, streetscape- and **access**- pedestrian crossings, parking, access management, network, and active transportation.

The project team studied existing conditions throughout the Main Street area that focused on access and placemaking, as well as analysis of the range of transportation modes served by Main Street- traffic, transit, bicycling, and walking. The team engaged Main Street business owners through a short survey.

In August 2021, the Kaysville/UDOT group came together at Kaysville City Hall for a workshop to develop ideas based on the identified shared priorities. The workshop yielded four alternative concepts with various approaches to sidewalk expansions, pedestrian crossings, medians, and parking solutions (see images at right).


The team presented the concepts to the group, which convened again in October to select a preferred concept. The group gravitated toward a mix of the concepts that became the Preferred Concept - a solution that is unorthodox and creative but still achieves the goals of both the community and UDOT.

The Kaysville Main Street process shows that focused, careful collaboration between UDOT and a local community that considers common goals can open the door to creative solutions.




ALTERNATIVE 1

Move crossing to midblock and smaller improvements




ALTERNATIVE 2

Historic storefront pedestrian realm expansion




ALTERNATIVE 3

Civic campus plaza enhancement



ALTERNATIVE 4

Full historic Main Street streetscape



much of the pathway could need to run immediately along the roadway, which will be without a shoulder or on-street parking as a buffer to moving traffic.

Implementation

Aspects of implementation discussed here include:

- Roles: Who will do what to get the project done.
- Funding: How the project's design, construction, and any other costs will be covered.
- Phasing : How the project will be broken up into manageable and feasible pieces, and which ones will happen first.
- Addressing key concerns: Anticipating concerns from stakeholders and the public that may arise, and how to address those concerns.

Below are considerations for each.

Roles

The Kaysville Main Street project will be a partnership. Kaysville City and UDOT will continue to work together, coordinating and meeting as needed as the project progresses.

Kaysville City will engage stakeholders and the broader community on the Preferred Concept for Main Street. The City will seek adoption of the Preferred Concept by the Mayor and City Council. The City will consider the extension of its downtown redevelopment area north of 200 North to encompass this project's study area, in order to capture tax increment to help fund the project. The City will work to identify a mix of potential funding sources and then work with UDOT to refine, continue to plan, design, and construct the project.

UDOT Region 1 will work with Kaysville City to establish and define the Main Street improvements as a distinct project and place it on the Statewide Transportation Improvements Program (STIP). UDOT will work with Kaysville to seek state and regional funding sources.

In case of desire to move or enhance bus stops to implement the concept, Kaysville and UDOT will seek to include **Utah Transit Authority (UTA)** as a partner.

Business and property owner stakeholders are also partners in the project, both from a planning and design standpoint, a logistics standpoint (construction management), and possibly from the standpoint of shaping or contributing to the streetscape improvements.

Funding

Appendix 1 is an initial high-level cost estimate for the Preferred Concept and identifies a rough cost of \$2.37 Million for the project, including all three Main Street blocks addressed in the concept. Several options exist to help pay for the project.

Local sources:

- Kaysville City General Fund or Capital Improvements Program
- Potential extension of downtown redevelopment area to the project study area and resulting tax increment financing (TIF) funds

UDOT sources:

- Transportation Investment Fund (TIF) Active
- Transportation Alternatives Program (TAP)
- Class B & C Road Funds

Other State funds:

- GO-UTAH Utah Main Street Program funds

Phasing

The project could be phased in a number of different ways. It could be built as one large project, from 200 North through 50 West. Or it could be divided into a few phases, each of which can work independently as a functional project until the other phases are added. The following are considerations:

- **Moving the HAWK from Center Street to mid-block** between Center Street and 100 North could be an initial “pre-phase” of the project, in order to begin the connection of the west side of the central block of Main Street with the civic campus and its parking. However, the placement of the HAWK pole on the west side available now is not likely optimal for the eventual project layout.
- **The central (civic) block improvements** could be implemented before those on the block to the north and the south. However, with the planned lateral transition of the lanes to the east and back, work would extend into the north and south blocks for this phase, so it might make sense to make any improvements there at the same time. In addition, the improvements on the north and south blocks constitute a relatively minor part of the overall improvements- there is little downside to do all three blocks at once.

In summary, each element of the concept does help reinforce and lead to the success of the others. If the project is broken up into phases, the concerns would be that temporary transitional fixes may be needed and the trade-offs of the concept would not be apparent. For example, street parking might be lost or changed but the public space improvements wouldn't have been built, not yet demonstrating the payoff for giving up parking.

Addressing potential concerns

The following are some potential concerns about the concept, based on conversation among the project committee, and initial thoughts on how to address those concerns.

Reconfiguration of parking: On-street parking in the Main Street area will be reconfigured to complement the concept, and especially along the central block of Main Street directly adjacent to the businesses in the historic storefronts the reconfiguration could be perceived as a loss of parking. Indeed, there will be fewer spaces directly adjacent to these businesses that rely on such parking. However, there are many considerations:

- The west side of Main Street in the central block would only lose an estimated six spaces.
- New diagonal parking on side streets will likely make up for the lost Main Street parking.
- In addition, the mid-block HAWK signalized crossing will make it easier for patrons, proprietors, and employees of these businesses to access the large parking lot across the street, in back of the City Hall.
- We hope that what is gained in public space by trading off the on-street parking is, especially in the long run, worth the loss.
- Part of the concept is a series of customer parking pockets on the west side of Main Street in the central block - on-street parking spaces with time restrictions.

Vehicle access: Main Street's current configuration generally allows open vehicle access on and off Main Street. The Main Street concept restricts this vehicle access on and off Main Street, which may force drivers to think more carefully about how they access certain Main Street destinations. But by implementing these restrictions, Main Street becomes easier and safer to use as a pedestrian and becomes safer for motorists as well, due to the potential conflicts with other vehicles eliminated.

Mobility on Main Street: The Main Street concept is designed to slow traffic between 50 West and 200 North. This may raise concerns about increases of travel time through this segment of Main Street (S.R. 273). Yet this is a very short segment that, at peak traffic times, often produces queues especially in the p.m. peak in the northbound direction. Slowing, combined with the access management improvements, are likely to smooth traffic flow.

Visibility: Introducing elements such as planted medians and streetscape can raise concerns about motorists being able to see crossing pedestrians or cyclists or other motorists. However, these additional elements are designed to create a slow environment for autos that reduces the speed, increasing available reaction time to react to other users in the roadway. Furthermore, creating a human scale for the street also engenders slow auto travel.

Special events: The Kaysville community has historically used Main Street for community events such as its 4th of July parade. There may be concerns about whether these events will thrive under the new configuration. We assert that parades and other community events will still thrive with the new medians and streetscape, and in some cases, will thrive more than the current configuration.



EXISTING STREET



VISION CONCEPT

APPENDIX: Draft Cost Estimate

KAYSVILLE MAIN STREET CONCEPT ESTIMATE - DRAFT

			Center to 100 N		50 W to Center		100 N to 200 N		Units	Combined Total	Combined Total Price	Price	Remarks
	Quantity	Cost	Quantity	Cost	Quantity	Cost	Quantity	Cost					
Road	015017010	Remove Tree	6	\$3,000	0	\$0	10	\$5,000	each	16	\$8,000.00	\$500	
	015547005	Remove Concrete Curb and Gutter	830	\$12,450	300	\$4,500	310	\$4,650	foot	1,440	\$21,600.00	\$15	
	01557001*	Remove Asphalt Pavement	1,920	\$28,800	440	\$6,600	180	\$2,700	square yard	2,540	\$38,100.00	\$15	
	022217050	Untreated Base Course (Plan Quantity)	100	\$2,000	90	\$1,800	90	\$1,800	cubic yard	280	\$5,600.00	\$20	
	022217125	Asphalt Pavement Soft Spot Repair - Type A	300	\$15,000	190	\$9,500	210	\$10,500	sq yd	700	\$35,000.00	\$50	
	022217165	HMA - 1/2 Inch	495	\$52,010	305	\$32,051	340	\$35,700	ton	1,141	\$119,761.69	\$105	
	027217020	HMA - Bike/Ped Path 1/2 Inch	130	\$14,950	120	\$13,800	120	\$13,800	ton	370	\$42,550.00	\$115	
	02737001*	Emulsified Asphalt CSS-1	1	\$500	1	\$500	1	\$500	ton	3	\$1,500.00	\$500	
	027417050	Detectable Warning Surface	10	\$5,000	6	\$3,000	2	\$1,000	each	18	\$9,000.00	\$500	
	027437040	Concrete Curb and Gutter Type B1	2,030	\$60,900	750	\$22,500	545	\$16,350	foot	3,325	\$99,750.00	\$30	
	027487040	Concrete Flatwork, 4 inch thick	24,050	\$240,500	4,220	\$42,200	5,050	\$50,500	square foot	33,320	\$333,200.00	\$10	
	027717086	Rotomilling - 1 1/2 Inch	5,950	\$47,600	3,670	\$29,360	4,010	\$32,080	square yard	13,630	\$109,040.00	\$8	
Drainage	026107386	Drainage Pipe - 18 inch, Smooth, Leak-Resistant	40	\$6,000	40	\$6,000	20	\$3,000	foot	100	\$15,000.00	\$150	
	026337130	Concrete Drainage Structure 5 ft to 7 ft deep - CB 9	2	\$10,000	2	\$10,000	1	\$5,000	each	5	\$25,000.00	\$5,000	
	018927050	Reconstruct Manhole	2	\$3,000	4	\$6,000	1	\$1,500	each	7	\$10,500.00	\$1,500	
Traffic	027657050	Pavement Marking Paint	40	\$2,000	42	\$2,100	40	\$2,000	gallon	122	\$6,100.00	\$50.00	
	027687105	Pavement Message (Preformed Thermoplastic)	2	\$800	2	\$800	10	\$4,000	each	14	\$5,600.00	\$400.00	
	027687110	Pavement Message (Preformed Thermoplastic Stop Line, Crosswalks - 12 inch)	310	\$4,650	140	\$2,100	160	\$2,400	ft	610	\$9,150.00	\$15.00	
	028917028	Sign Type A-1, 12 Inch X 36 Inch	5	\$500	5	\$500	5	\$500	each	15	\$1,500.00	\$100.00	
	028917270	Remove Sign Less Than 20 Square Feet	2	\$60	2	\$60	2	\$60	each	6	\$180.00	\$30.00	
	028917285	Relocate Sign Less Than 20 Square Feet	8	\$1,600	6	\$1,200	5	\$1,000	each	19	\$3,800.00	\$200.00	
Environmental		Landscaping w/topsoil, sod and irrigation	3,115	\$46,725	700	\$10,500	655	\$9,825	square foot	4,470	\$67,050.00	\$15.00	
		New Tree, 2 inch caliper	25	\$16,250	15	\$9,750	10	\$6,500	each			\$650.00	

Totals	\$574,300	\$214,820	\$210,370	\$999,490.00
Totals (no path)	\$557,350	\$199,220	\$194,770	\$951,340.00
Totals (no mill + fill)	\$459,690	\$143,910	\$132,090	\$735,690.00
Totals (no mill + fill and no path)	\$442,740	\$128,310	\$116,490	\$687,540.00

subtotal \$951,340 no path, all 3 blocks

#N/A	Traffic Signal System (RELOCATE HAWK)	1	\$150,000
16525701D	Highway Lighting System	1	\$100,000

subtotal \$1,201,340

015017010	Mobilization	1	\$121,000	Usually 7-10% of construction
015547005	Traffic Control	1	\$61,000	Usually 3-5% of construction
01557001*	Maintenance of Traffic	1	\$13,000	Usually 1% of construction
015407010	Public Information Services	1	\$4,000	Usually 0.25% of construction

Subtotal \$1,400,340
Contingency 20.00% \$280,070
Construction Total \$1,680,410

PE Subtotal 8% \$134,430
CE Subtotal 10% \$168,040
Aesthetics 0.75% \$12,610
Change Order Contingency 9% \$151,240

Total \$2,146,730

Assumed Inflation for 2025 3.25% \$2,363,000

Assumed 5% of total mill and fill area for full depth patching (soft spot repair)
Assumed no additional subbase work (beyond Flatwork) for concrete replacement/expansion
Assumed 11' lanes, crown in center of existing center lane.
Assumed lighting cost prorated for distance based off another project
Assumed \$100,000 for HAWK relocation (original cost)
Assumed \$50,000 to move HAWK cabinet, etc (was already there for original HAWK project)
General pavement + base costs for HMA paths, this does not take into consideration the impacts which are considerable



Kaysville City Redevelopment Agency
Kaysville City Center Reinvestment Area
***DRAFT* Project Area Budget**
January 30, 2024

KAYSVILLE CITY CENTER | CRA PROJECT AREA BUDGET

The following narrative has been prepared in accordance with Utah Code §17C-5-303 for an Agency that receives tax increment.

This Budget is prepared in good faith as a current reasonable estimate of the economic impact of projected development and redevelopment within the Project Area. Fundamental economic and other circumstances may influence the actual impact. With these assumptions, the information contained within this Budget represents the reasonable expectations of the Agency. Due to multiple factors beyond our control, the Agency makes no guarantee that the projections contained in this Budget of the Project Area Plan for the Project Area will accurately reflect the future development and/or redevelopment within the Project Area. Further, the Agency specifically reserves all powers granted to it under the Act, now and as may be amended; this Budget shall not be interpreted to limit or restrict the powers of the Agency as granted by the Act. The actual amount of tax increment received by the Agency will be determined solely by interlocal agreement(s) between the Agency and the various taxing entities; this Budget does not control the flow of tax increment money, nor does it entitle the Agency to receive money from tax increment or any other source.

1(A). THE BASE TAXABLE VALUE [17C-5-303(1)(A)]

The base year taxable value is the year 2023 value of \$203,550,124.

1(B). PROJECTED AMOUNT OF TAX INCREMENT TO BE GENERATED WITHIN THE PROJECT AREA [17C-5-303(1)(B)]

The overall total projected amount of tax increment to be generated within the Project Area over 15 years is \$8,302,933.

TABLE 1: INCREMENTAL PROPERTY TAX REVENUES FOR 15 YEARS

Taxing Entities	Total	NPV*
Davis County	\$982,333	\$626,825
Multicounty Assessing & Collecting Levy	\$12,791	\$8,162
County Assessing & Collecting Levy	\$111,706	\$71,280
Davis County School District	\$5,310,739	\$3,388,774
Kaysville	\$1,331,948	\$849,914
Weber Basin Water Conservancy District	\$170,544	\$108,824
Davis County Mosquito Abatement District	\$83,567	\$53,324
Central Davis County Sewer District	\$99,768	\$63,662
County Library	\$199,536	\$127,324
TOTAL	\$8,302,933	\$5,298,089
*NPV = net present value discounted at 3 percent		

1(c). PROJECT AREA FUNDS COLLECTION PERIOD [17C-5-303(1)(c)]

The collection period is 15 years.

1(d). PROJECTED AMOUNT OF TAX INCREMENT TO BE PAID TO OTHER TAXING ENTITIES [17C-5-303(1)(d)]**TABLE 2: INCREMENTAL PROPERTY TAX REVENUES PAID TO TAXING ENTITIES FOR 15 YEARS**

Taxing Entities	Total	NPV*
Davis County	\$392,933	\$250,730
Multicounty Assessing & Collecting Levy	\$12,791	\$8,162
County Assessing & Collecting Levy	\$111,706	\$71,280
Davis County School District	\$2,124,296	\$1,355,510
Kaysville	\$266,390	\$169,983
Weber Basin Water Conservancy District	\$68,218	\$43,530
Davis County Mosquito Abatement District	\$33,427	\$21,329
Central Davis County Sewer District	\$39,907	\$25,465
County Library	\$79,815	\$50,930
TOTAL	\$3,129,482	\$1,996,917
*NPV = net present value discounted at 3 percent.		

1(e). IF THE AREA FROM WHICH TAX INCREMENT IS COLLECTED IS LESS THAN THE ENTIRE PROJECT AREA [17C-5-303(1)(e)]

Not applicable.

1(f). THE PERCENTAGE OF TAX INCREMENT THE AGENCY IS AUTHORIZED TO RECEIVE [17C-5-303(1)(f)]

We propose the Agency is authorized to receive 60 percent of the tax increment for a period of 15 years from participating taxing entities, including Davis County, Davis County School District, Weber Basin Water Conservancy District, Davis County Mosquito Abatement District, Central Davis County Sewer District and the County Library. Kaysville City would participate at a rate of 80 percent. The projected dollar amount of increment going to the Agency would be \$5,173,451.

1(g). THE MAXIMUM CUMULATIVE DOLLAR AMOUNT OF TAX INCREMENT THE AGENCY IS AUTHORIZED TO RECEIVE FROM THE PROJECT AREA [17C-5-303(1)(g)]

The maximum dollar amount the Agency is authorized to receive is proposed to be \$10,000,000. Note that out of this amount, the Agency will have administrative expense and housing payments.

2. IF THE AGENCY RECEIVES SALES AND USE TAX REVENUE [17C-5-303(2)(a) AND (b)]

Not applicable.

3. AMOUNT OF PROJECT AREA FUNDS THE AGENCY WILL USE TO IMPLEMENT THE PROJECT AREA [17C-5-303(3)]

The Agency approximates its funds will be used as follows but reserves the right to maintain flexibility and not strictly adhere to the items listed below. All Agency funds will be used for infrastructure, economic development or administrative purposes within the Project Area. Administrative funds have been calculated based on three percent of Agency tax increment receipts annually. In addition, ten percent of Agency receipts have been set aside for housing projects. Housing funds do not need to be spent within the Project Area. The remaining funds would be generally allocated as follows:

- Main Street improvements between 200 North and 100 South, including expansion, installation of medians, intersection realignment, and traffic calming (~\$2,363,000)
- Other roadway and intersection improvements (~\$800,000)
- Beautification and landscaping (~\$250,000)
- Sidewalk expansion or realignment, trail development, etc. (~\$500,000)
- Creation of pedestrian oriented atmosphere and facilities (~\$250,000)
- Creation of public open space amenities (~\$190,000)
- Property acquisition (~\$2,000,000)
- Parking enhancements, parking structure and facilities (~\$5,000,000)
- Traffic, circulation and parking studies (~\$35,000)
- Relocation assistance for businesses and or residences (~\$350,000)
- Location assistances for businesses (~\$150,000)
- Demolition and pre-demolition environmental assessment costs (~\$20,000)
- Utility expansion, extension or upgrades (~\$250,000)
- Installation of fiber optic networks (~\$200,000)
- Facilitation of façade grant and loan programs (~\$200,000)
- Relocation of historical markers (~\$75,000)

4. THE AGENCY'S COMBINED INCREMENTAL VALUE [17C-5-303(4)]

The total incremental value in the Kaysville City Center Project Area is estimated at approximately \$76,511,400 at buildout.

The City has one additional project area in place, the Flint Street CDA, with an incremental value of \$27,715,391 in 2022.

5. THE AMOUNT OF PROJECT AREA FUNDS THAT WILL BE USED TO COVER THE COST OF ADMINISTERING THE PROJECT AREA [17C-5-303(5)]

The Agency is requesting that three percent of revenues received be set aside for administrative purposes. The projected total amount of administrative cost over the 15-year timeframe is approximately \$155,204 to the Kaysville City Redevelopment Agency and another \$17,682 to the County for administrative costs.

6. FOR PROPERTY THAT THE AGENCY OWNS AND EXPECTS TO SELL, THE EXPECTED TOTAL COST OF THE PROPERTY TO THE AGENCY AND THE EXPECTED SALE PRICE [17C-5-303(6)]

Not applicable.

DRAFT